

ADDENDUM No. 2

ITB No. 4691

Sanitary Manhole Raising Project

Bids Due: November 23, 2021 by 2:00 P.M. (Local Time)

The information contained herein shall take precedence over the original documents and all previous addenda (if any) and is appended thereto. **This Addendum includes three (3) pages.**

Bidder is to acknowledge receipt of this Addendum No. 2, including all attachments (if any) in its Bid by so indicating on page ITB-1 of the Invitation to Bid Form. Bids submitted without acknowledgment of receipt of this addendum may be considered nonconforming.

The following forms provided within the ITB document should be included in submitted bids:

- City of Ann Arbor Prevailing Wage Declaration of Compliance
- City of Ann Arbor Living Wage Ordinance Declaration of Compliance
- Vendor Conflict of Interest Disclosure Form
- City of Ann Arbor Non-Discrimination Ordinance Declaration of Compliance

Bids that fail to provide these forms listed above upon bid opening may be rejected as non-responsive and may not be considered for award.

I. CORRECTIONS/ADDITIONS/DELETIONS

Changes to the Bid document which are outlined below are referenced to a page or Section in which they appear conspicuously. The Bidder is to take note in its review of the documents and include these changes as they may affect work or details in other areas not specifically referenced here.

All mentions As provided in ITB No. 4691 Bid Document:
Complete the entire project on or before June 30, 2022.

As updated herein:
Complete the entire project on or before December 31, 2022.

All mentions As provided in ITB No. 4691 Bid Document:
Bid Form – Section 1 – Schedule of Prices

As updated herein:
Addendum #2 – Bid Form – Section 1 – Schedule of Prices

Comment: Updating Bid Form to add pay item #24, "Temporary No Parking Signs" to the bid form along with the Detailed Specification for this added pay item as provided herein.

Bidders are responsible for any conclusions that they may draw from the information contained in the Addendum.

ADDENDUM #2 - BID FORM

Section 1 – Schedule of Prices

Company: _____

Project: **Sanitary Manhole Raising Project**

Item	Description	Unit	Est. Qty	Unit Price	Extended Price
1	General Conditions, Max \$10,000	LS	1	\$	\$
2	Curb, Gutter, and Curb and Gutter, Any Type, Rem	LF	100	\$	\$
3	Curb and Gutter, Conc, Barrier	LF	50	\$	\$
4	Curb and Gutter, Conc, Mountable	LF	50	\$	\$
5	Curb and Gutter, Conc, Det M, Modified	LF	50	\$	\$
6	Sidewalk, Sidewalk Ramp, and Driveway Approach, Any Thickness, Rem	SYD	100	\$	\$
7	Driveway, Nonreinf Conc, 6 Inch, Modified	SYD	50	\$	\$
8	Driveway, Nonreinf Conc, 8 Inch, Modified	SYD	50	\$	\$
9	Sidewalk, Conc, 4 inch, Modified	SFT	300	\$	\$
10	Sidewalk, Conc, 6 inch, Modified	SFT	300	\$	\$
11	Sidewalk, Conc, 8 inch, Modified	SFT	250	\$	\$
12	Sidewalk Ramp, Conc, 6 inch, Modified	SFT	100	\$	\$
13	Detectable Warning Surface	SFT	50	\$	\$
14	Dr Structure Cover, Adj, Case 1, Conc Pvmt	EACH	20	\$	\$
15	Dr Structure Cover, Adj, Case 1, HMA Pvmt	EACH	75	\$	\$
16	Dr Structure Cover, Adj, Case 2, Outside of Pavement	EACH	175	\$	\$
17	Dr Structure Cover, Adj, Case 3, Driveway or Sidewalk	EACH	10	\$	\$
18	Dr Structure, Adj, Add Depth	FT	250	\$	\$
19	Manhole Locate, Any Depth, Below Grade, Any Method	EACH	50	\$	\$
20	Manhole Locate, Any Depth, Above Grade, Any Method	EACH	200	\$	\$
21	Internal Chimney Seal	EACH	25	\$	\$
22	Reconstruct Flow Channel	EACH	25	\$	\$
23	Minor Traffic Control, Max \$5,000	LS	1	\$	\$
24	Temporary No Parking Signs	EACH	50	\$	\$
25	Temporary Traffic Control, Standard	DAY	50	\$	\$
26	Temporary Traffic Control, Complex	DAY	25	\$	\$
27	Temporary Traffic Control, Special	DAY	10	\$	\$
28	Mobilization, Emergency	EACH	10	\$	\$
29	Mobilization, Non-Emergency	EACH	5	\$	\$
	Total Bid			\$	

CITY OF ANN ARBOR
DETAILED SPECIFICATION
FOR
TEMPORARY NO PARKING SIGNS

AA:DAD

1 of 1

03/11/19

a. Description. This work consists of installing, maintaining and removing of "No Parking" signs and posts as outlined herein and as referenced on the plans. Install "No Parking" signs in accordance with the section 812 of the Michigan Department of Transportation (MDOT) 2012 Standard Specifications for Construction Standard Specifications and the 2011 Michigan Manual of Uniform Traffic Control Devices (MMUTCD).

b. Materials. The City will furnish "No Parking" signs to the Contractor at no cost. The Contractor will furnish the sign support and mounting hardware materials in accordance with those specified in section 919 of the MDOT 2012 Standard Specifications for Construction.

c. Construction. Place temporary "No Parking" signs prior to the commencement of any construction activity as directed by the Engineer. Obtain a permit for "Temporary Permission of Reserve Parking Lane for Work Related Purposes" from the City's Engineering Unit. Obtain this permit a minimum of five (5) business days prior to the posting of "No Parking" signs.

Securely bolt the signs to the sign supports as directed by the Engineer. Imbed all sign supports at least two feet into the ground, and ensure that installations are stable and safe. Provide a minimum six feet and maximum seven feet of clearance between the bottom of the installed sign and the ground. Place signs at intervals no greater than 75 feet, and as necessary to eliminate parking in the construction area.

Install temporary "No Parking" signs be in accordance with the permit, as as directed by the Engineer, and at least 48 hours prior to the proposed start-of-work/enforcement date. Cover temporary "No Parking" signs to allow for on-street parking until 48 to 24 hours prior to the start of the work. Cover temporary "No Parking" signs during non-working periods longer than 72 hours. Prior to beginning work and during construction, cover existing/permanent "No Parking" signs having messages that conflict with those that are temporary. Remove temporary "No Parking" signs and posts upon the completion of work at each location. Return signs to the City upon completion of all contract work, and/or when no longer needed.

d. Measurement and Payment. Measure and pay for the completed work, as described, at the contract unit price using the following pay item:

<u>Pay Item</u>	<u>Pay Unit</u>
Temporary No Parking Sign	Each

Measure **Temporary No Parking Sign** individually in place by the unit each and pay for it at the contract unit price, which price includes all cost for labor, equipment and materials necessary to complete the work. Measurement will be for the maximum number of signs installed on a project location at any one time. The unit price also includes the removal and return of "No Parking" signs to the City upon completion of the project, and the covering of any existing/permanent "No Parking" signs.

The City will back charge the Contractor for replacement costs associated with damaged and/or unreturned signs.