



Radon Measurement Assessment Report

Prepared for:

**Ann Arbor Housing Commission
2000 South Industrial
Ann Arbor, MI 48104**

Project location:

**Lurie Terrace
600 West Huron
Ann Arbor, MI 48103**

PE Project Number:

MI22-1033

Prepared by:

**Protect Environmental
9822 Bluegrass Parkway
Louisville, KY 40299
Phone: 502-410-5000
ProtectEnvironmental.com**

Report Date:

December 23, 2022

Prepared by:

Keith Hoylman
Protect Environmental

Preparation Date: December 23, 2022

This assessment report was developed specifically for the radon measurement conducted at Lurie Terrace, 600 West Huron, Ann Arbor, MI 48103. The measurement was conducted in accordance with the document *Protocol for Conducting Radon and Radon Decay Product Measurements in Multifamily Buildings (ANSI/AARST MAMF 2017)* by Jimmy Rogers, a radon measurement professional credentialed by the National Radon Proficiency Program (NRPP).

Please direct inquiries regarding this report to Jennifer Sims at 502-272-2662 or Jennifer@ProtectEnv.com.



Keith Hoylman
Radon Professional
NRPP Certification Number: RMT-109309

Contents

- 1.0 Introduction and Summary
- 2.0 Scope of Work
- 3.0 Measurement Protocol and Quality Assurance
- 4.0 Measurement Devices
- 5.0 Measurement Conditions
- 6.0 Findings, Recommendations and Required Advisories

Appendices

- 1.0 Appendix A: Analytical Laboratory Report
- 2.0 Appendix B: Device Placement Log
- 3.0 Appendix C: Quality Assurance Documentation
- 4.0 Appendix D: Measurement Event Weather Conditions
- 5.0 Appendix E: Professional Certification Documentation
- 6.0 Appendix F: EPA Radon Zone Map
- 7.0 Appendix G: Notification Documentation

Section 1.0 – Introduction and Summary

1.1 Purpose

Radon is a colorless, odorless, radioactive gas formed through the decay of uranium. Trace amounts of uranium is present in all soil, and radon is found all over the planet. Most of this gas remains underground, but a small percentage migrates to the surface. Most radon is diluted in the atmosphere to very low concentrations but can build up to high concentrations in buildings. The amount of radon intruding into a building depends on the strength of the source, preferential pathways into the building, and a driving force (usually the thermal stack effect of the building). While two buildings may be identical, each site is unique. The only way to know what the radon levels are inside a building is through measurement. Two structures side-by-side can have totally different radon levels.

Radon is the second leading cause of lung cancer in the general population and the leading cause of lung cancer among non-smokers. Radon exposure is the cause of approximately 21,000 U.S. lung cancer deaths each year. This risk is largely preventable through testing and mitigation.

For more information on radon, please contact:

- The Michigan Department of Environment, Great Lakes, and Energy, Materials Management Division at **517-284-6551** or visit their website at https://www.michigan.gov/egle/0,9429,7-135-3312_4120_4196---,00.html
- The US Environmental Protection Agency at **1-800-767-7236** or visit their website at <https://www.epa.gov/radon>.

1.2 Property Information

Protect Environmental was engaged to conduct a radon measurement and assessment at the subject property located at Lurie Terrace, 600 West Huron, Ann Arbor, MI 48103. Prior to the measurement, the client or designated representative did not indicate that active mitigation systems were currently in operation at the property.

The property is located within an EPA Zone 1 county.

EPA Zones:

- Zone 1- Average radon levels at or above 4.0 pCi/L
- Zone 2- Average radon levels between 2.0 and 3.9 pCi/L
- Zone 3- Average radon levels at or below 1.9 pCi/L

The EPA Radon Zone designation should not be used to determine if a property should be tested. All buildings should be tested for radon, regardless of location or EPA Radon Zone designation.

1.3 Measurement Summary

The measurement was conducted between December 19 and 21, 2022, and was requested as part of a due diligence project being conducted by the client. A total of 35 measurement devices to be deployed in 31 residential and 4 non-residential locations in 1 building were included in the measurement and quality assurance project plan. The measurement included 1 vacant location. For quality assurance purposes, 4 duplicate and 2 field blank measurement devices were deployed. All devices were sent under appropriate chain of custody to a qualified analytical laboratory for analysis.

Findings and recommendations regarding the analytical lab results and corresponding assessment are provided in Section 6.1 of this report.

Section 2.0 – Scope of Work

The assessment includes the following scope of work components:

1. Conducting an initial planning meeting with the client to review the project scope, information necessary to build the measurement and quality assurance project plan, required conditions and on-site logistics.
2. Preparing and implementing a measurement and quality assurance project plan for the assessment, in accordance with the required measurement protocol.
3. Placing and retrieving the measurement devices, preparation of chain of custody documentation and shipping of the devices to a qualified analytical laboratory for analysis, and interpretation of the analytical laboratory data.
4. Providing the client with a written report of the measurement findings and recommendations.

Section 3.0 – Measurement Protocol and Quality Assurance

The measurement was conducted in accordance with the document *Protocol for Conducting Radon and Radon Decay Product Measurements in Multifamily Buildings (ANSI/AARST MAMF 2017)* by Jimmy Rogers, a radon measurement professional credentialed by the NRPP. Field Professional certification documentation is attached as Appendix E to this report.

Quality assurance measures were conducted in accordance with ANSI/AARST MAMF 2017. Details regarding the QA procedures implemented for this project are included in Appendix C of this report.

Section 4.0 – Measurement Devices

Liquid scintillation devices manufactured by RAdata, LLC were utilized for the measurements. All devices were forwarded under appropriate chain of custody for analysis by RAdata, LLC, an analytical laboratory credentialed by the NRPP. Each device was deployed in accordance with the instructions provided by the manufacturer. The chain of custody for measurement devices is available on request.

RAdata, LLC
27 Ironia Road, Unit 2
Flanders, NJ 07836
NRPP License Number: 101196AL

Section 5.0 – Measurement Conditions

The occupant of each location at the property was notified of the required measurement conditions to be maintained during the testing event prior to device placement. The field professional also delivered notification of the required measurement conditions applicable to the testing event at the time of device placement. In addition, the responsible party for the overall testing event was notified of the required measurement conditions to be maintained during the testing event prior to device placement. Notifications are attached as Appendix G to this report.

Compliance with the measurement conditions and non-interference controls contained within the measurement protocol was verified by the field professional placing and retrieving the measurement devices. At the time of the measurement, violations of the required measurement conditions or evidence of device tampering were not observed by the field professional, unless noted within this report. Modifications to the measurement and quality assurance project plan were not made by the field professional, unless noted within this report. Weather conditions that existed during the measurement event are attached as Appendix D to this report.

Section 6.0 – Findings, Recommendations and Required Advisories

The sole purpose of this assessment is to provide the client with information regarding the indoor radon concentrations at the property at the time of the measurement. An uncertainty with any test result due to statistical variations and other factors, such as daily and seasonal variations in indoor radon concentrations, does exist. Variations may occur due to changes in weather conditions, building usage or possible unobserved interference with the required measurement conditions. Locations not occupied, able to be occupied or inaccessible at the time of the measurement were not tested. Any location not occupied, able to be occupied or inaccessible at the time of the measurement should be tested to ensure radon levels are below the EPA action level prior to future occupancy or upon accessibility, as applicable. The findings and recommendations contained within this report are derived

from information obtained from the client and their designated representative, the on-site activities and analytical services provided under the scope of work performed. No representation is made in this report regarding the operational status or proper operation of any mitigation system(s) that may be installed at the property. This measurement assessment report was prepared solely for the use of the client. Use of this report by any party other than is prohibited without prior written consent from Protect Environmental.

6.1 Findings and Recommendations

Based upon the analytical lab results, the locations contain indoor radon concentrations below the EPA action level of 4.0 pCi/L. The quality assurance plan for the project was in control. No additional action is recommended.

6.2 Required Advisories

When a location is indicated to have radon levels below the EPA action level of 4.0 pCi/L:

1. If the location is indicated to have radon levels below the EPA action level of 4.0 pCi/L but at or above 2.0 pCi/L, consider mitigation of the building.
2. When the initial measurement is conducted under non-heating season conditions, follow-up measurement of all buildings under heating season at the earliest opportunity, and no later than 5 years after the initial measurement is recommended.
3. Consideration is recommended to alternate future measurements to obtain results under a different season that represents a significant portion of the yearlong operating condition for the building.
4. A follow-up measurement is recommended at least every 5 years and in conjunction with the sale of a building(s); a new addition is constructed or significant alterations occur; a ground-contact location not previously tested is occupied; HVAC systems are altered with resulting changes to air distribution or pressure relationship; ventilation is altered by extensive weatherization or changes to mechanical systems; sizeable openings due to ground water or slab surface water control systems are added or altered; natural settlement causing major cracks develops; earthquakes or construction blasting occur nearby; a mitigation system is altered, repaired or modified.

Appendix A

Analytical Laboratory Report



Original Report Date: December 23, 2022

Protect Environmental
 Winnie Cheuvront
 9822 Bluegrass Pkwy
 Louisville, KY 40299

Radon Test Results/Information:

FileNum: MI22-1033

Name: Lurie Terrace,
 Test Location: 600 West Huron, Ann Arbor MI 48103

Test #	Test Date	Test Device	Location	Avg. Radon Concentration	Date Analyzed
Room #: Reception					
1495900-1496434	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.2 pCi/L +/- 0.37	12/22/2022,22:35 Analyzed by: David Rojas
Room #: 107					
1495901-1496435	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	< 0.2 pCi/L	12/23/2022,00:14 Analyzed by: David Rojas
Room #: 705					
1495902-1496436	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Above Third Floor	0.9 pCi/L +/- 0.37	12/23/2022,00:49 Analyzed by: David Rojas
Room #: 621					
1495903-1496437	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Above Third Floor	0.6 pCi/L +/- 0.36	12/23/2022,00:38 Analyzed by: David Rojas
Room #: 106					
1495910-1496444	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.3 pCi/L +/- 0.38	12/22/2022,23:41 Analyzed by: David Rojas
Room #: 107					
1495911-1496445	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.3 pCi/L +/- 0.38	12/23/2022,00:03 Analyzed by: David Rojas
Room #: 725					
1495912-1496446	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Above Third Floor	0.6 pCi/L +/- 0.36	12/23/2022,01:00 Analyzed by: David Rojas
Room #: 612					
1495913-1496447	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Above Third Floor	0.7 pCi/L +/- 0.36	12/23/2022,00:27 Analyzed by: David Rojas
Room #: Main Office					
1495920-1496454	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.3 pCi/L +/- 0.38	12/22/2022,22:24 Analyzed by: David Rojas
Room #: 108					
1495921-1496455	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.3 pCi/L +/- 0.38	12/23/2022,00:36 Analyzed by: David Rojas
Room #: 827					
1495922-1496456	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Above Third Floor	0.8 pCi/L +/- 0.37	12/23/2022,01:11 Analyzed by: David Rojas

Test #	Test Date	Test Device	Location	Avg. Radon Concentration	Date Analyzed
Room #: 511					
1495923-1496457	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Above Third Floor	0.4 pCi/L +/- 0.34	12/23/2022,00:59 Analyzed by: David Rojas
Room #: Occ Spec Office					
1495930-1496464	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.2 pCi/L +/- 0.37	12/22/2022,22:02 Analyzed by: David Rojas
Room #: 108					
1495931-1496465	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.2 pCi/L +/- 0.38	12/23/2022,00:25 Analyzed by: David Rojas
Room #: 127					
1495932-1496466	12/19/2022,11:00-12/21/2022,10:00	Liquid Scintillation	First Floor	1.9 pCi/L +/- 0.49	12/22/2022,23:42 Analyzed by: David Rojas
Room #: 519					
1495933-1496467	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Above Third Floor	0.5 pCi/L +/- 0.36	12/23/2022,01:10 Analyzed by: David Rojas
Room #: 9					
1495940-1496474	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	Basement	1.1 pCi/L +/- 0.44	12/22/2022,23:08 Analyzed by: David Rojas
Room #: 109					
1495941-1496475	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.3 pCi/L +/- 0.39	12/23/2022,00:47 Analyzed by: David Rojas
Room #: 126					
1495942-1496476	12/19/2022,11:00-12/21/2022,10:00	Liquid Scintillation	First Floor	2.0 pCi/L +/- 0.50	12/22/2022,23:31 Analyzed by: David Rojas
Room #: 423					
1495943-1496477	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Above Third Floor	0.3 pCi/L +/- 0.33	12/23/2022,00:48 Analyzed by: David Rojas
Room #: Conf. Room					
1495950-1496484	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.3 pCi/L +/- 0.37	12/22/2022,22:13 Analyzed by: David Rojas
Room #: 109					
1495951-1496485	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.5 pCi/L +/- 0.40	12/23/2022,00:58 Analyzed by: David Rojas
Room #: 125					
1495952-1496486	12/19/2022,11:00-12/21/2022,10:00	Liquid Scintillation	First Floor	1.3 pCi/L +/- 0.44	12/22/2022,23:20 Analyzed by: David Rojas
Room #: 410					
1495953-1496487	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Above Third Floor	0.3 pCi/L +/- 0.34	12/23/2022,00:37 Analyzed by: David Rojas
Room #: 8					
1495960-1496494	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	Basement	1.1 pCi/L +/- 0.44	12/22/2022,22:57 Analyzed by: David Rojas
Room #: 110					
1495961-1496495	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.5 pCi/L +/- 0.40	12/23/2022,01:09 Analyzed by: David Rojas
Room #: 124					
1495962-1496496	12/19/2022,11:00-12/21/2022,10:00	Liquid Scintillation	First Floor	1.4 pCi/L +/- 0.45	12/22/2022,23:09 Analyzed by: David Rojas

Test #	Test Date	Test Device	Location	Avg. Radon Concentration	Date Analyzed
Room #: 309					
1495963-1496497	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Third Floor	0.4 pCi/L +/- 0.35	12/23/2022,00:15 Analyzed by: David Rojas
Room #: 106					
1495970-1496504	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.2 pCi/L +/- 0.37	12/22/2022,23:52 Analyzed by: David Rojas
Room #: 112					
1495971-1496505	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.3 pCi/L +/- 0.36	12/22/2022,22:03 Analyzed by: David Rojas
Room #: 123					
1495972-1496506	12/19/2022,11:00-12/21/2022,10:00	Liquid Scintillation	First Floor	0.8 pCi/L +/- 0.40	12/22/2022,22:58 Analyzed by: David Rojas
Room #: 326					
1495973-1496507	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Third Floor	0.4 pCi/L +/- 0.34	12/23/2022,00:26 Analyzed by: David Rojas
Room #: 8					
1495980-1496514	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	Basement	0.9 pCi/L +/- 0.43	12/22/2022,22:46 Analyzed by: David Rojas
Room #: 119					
1495981-1496515	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	1.1 pCi/L +/- 0.44	12/22/2022,22:14 Analyzed by: David Rojas
Room #: 122					
1495982-1496516	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	2.1 pCi/L +/- 0.51	12/22/2022,22:47 Analyzed by: David Rojas
Room #: 221					
1495983-1496517	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Second Floor	0.3 pCi/L +/- 0.34	12/23/2022,00:04 Analyzed by: David Rojas
Room #: 105					
1495990-1496524	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	0.2 pCi/L +/- 0.37	12/22/2022,23:19 Analyzed by: David Rojas
Room #: 120					
1495991-1496525	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	2.6 pCi/L +/- 0.54	12/22/2022,22:25 Analyzed by: David Rojas
Room #: 121					
1495992-1496526	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	1.2 pCi/L +/- 0.44	12/22/2022,22:36 Analyzed by: David Rojas
Room #: 208					
1495993-1496527	12/19/2022,00:00-12/21/2022,10:00	Liquid Scintillation	Second Floor	0.3 pCi/L +/- 0.33	12/22/2022,23:53 Analyzed by: David Rojas
Room #: 105					
1496342-1496888	12/19/2022,11:00-12/21/2022,09:00	Liquid Scintillation	First Floor	< 0.2 pCi/L	12/22/2022,23:30 Analyzed by: David Rojas

Test #	Test Date	Test Device	Location	Avg. Radon Concentration	Date Analyzed
--------	-----------	-------------	----------	--------------------------	---------------

The results of this measurement provide an idea of the average concentration in the area of the structure tested during this testing period. The actual risk depends upon the amount of time you are exposed to this concentration. The US EPA and the Center of Disease Control have used a continuous exposure level of 4.0 pCi/L as a guidance level at which remedial action is indicated. If you would like additional information on radon, we recommend that you contact either your state agency or the US EPA.

The accuracy of the radon levels determined at the time of sampling are dictated by proper deployment and conditions in the field. Since deployment in the field is not completed by Radata, Inc. laboratory personnel, the radon results indicated represent the levels found in the test device as received at our lab.

Charcoal Canister samples are analyzed by Method [EPA-402-R-92-004 July 92]
 Liquid Scintillation samples are analyzed by Method [EPA-402-R-92-004 July 92]
 (+/- = 2 sigma (95% confidence level) counting uncertainty reported in pCi/L.)

LIMITATIONS OF DATA AND PRODUCT LIABILITY

This product is designed to detect radon levels in a specific location. It can not guarantee the overall level of radon present in a home or building, or that people will not be exposed to potentially harmful levels of radon. The cost of this product is based solely on the value of the monitoring, and is unrelated to the value of any customers' property or health. RAdata, Inc. EXPRESSLY DISCLAIMS ALL LIABILITY FOR ANY SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING BUT NOT LIMITED TO DAMAGES RESULTING FROM THE IMPROPER USE OF THE PRODUCT OR THE IMPROPER INTERPRETATION OF THE DATA GENERATED BY THE PRODUCT. RAdata's AND ITS AGENTS SOLE AND EXCLUSIVE LIABILITY AND THE CUSTOMER'S SOLE LIABILITY AND EXCLUSIVE REMEDY WILL NOT EXCEED THE LESSER OF THE COST OF REPAIR OR REPLACEMENT OF THE PRODUCT. Neither RAdata, Inc. nor its agents accepts any liability for improper deployment of any device and shall not be responsible for the consequences of the results derived from same.

Confidentiality Notice: These test results, including any attachments are for the sole use of the intended recipient(s) and may contain confidential and privileged information. Any unauthorized review, use, copying, disclosure, or distribution by other than the intended recipient or authorized agent is prohibited. RAdata, LLC will not disclose to anyone the identification of a client or results of sample analysis without the expressed consent of the client, except where required by law or by state/federal agency. In situations where information or results are being subpoenaed by a regulatory agency or the courts, RAdata, LLC will notify the client promptly.

Jennifer Fusco, Laboratory Director

Appendix B

Device Placement Log

Device Placement Log

Facility:		Lurie Terrace				RES Devices:	31	Placement Arrival:	11:00 AM	
Address:		600 West Huron, Ann Arbor, MI 48103				NR Devices:	4	Placement Departure:	12:00 AM	
Contact:		Tim Olivier: 734-794-6720				Duplicate Devices:	4	Retrieval Arrival:	9:00 AM	
Placement Day/Type/Pro:	12/19/2022	ST	Jimmy Rogers			Blank Devices:	2	Retrieval Departure:	10:00 AM	
Retrieval Day/Type/Pro:	12/21/2022	ST	Jimmy Rogers			Total Devices:	41	Ship Info:	FedEx: 1-Day	
Standard:	MAMF 2017	Project Type:	HUD, Initial 100%			Shipped Devices:	41	Ship Date:	12/21/2022	
Kit Number	Start Date	Start Time	End Date	End Time	Temp	Building	Room	Floor	Vacant	Notes
1495930	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		Occ Spec Office	1		
1495950	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		Conf. Room	1		
1495920	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		Main Office	1		
1495900	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		Reception	1		
1495980	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		8	0		
1495960	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		8 DUPLICATE	0		
1495940	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		9	0		
1495990	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		105	1		
1496342	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		105 FIELD BLANK	1		
1495910	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		106	1		

Device Placement Log

1495970	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		106 DUPLICATE	1		
1495911	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		107	1		
1495901	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		107 FIELD BLANK	1		
1495931	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		108	1		
1495921	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		108 DUPLICATE	1		
1495941	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		109	1		
1495951	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		109 DUPLICATE	1		
1495961	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		110	1		
1495971	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		112	1		
1495981	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		119	1		
1495991	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		120	1		
1495992	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		121	1		

Device Placement Log

1495982	12/19/2022	11:00 AM	12/21/2022	9:00 AM	75		122	1		
1495972	12/19/2022	11:00 AM	12/21/2022	10:00 AM	75		123	1		
1495962	12/19/2022	11:00 AM	12/21/2022	10:00 AM	75		124	1		
1495952	12/19/2022	11:00 AM	12/21/2022	10:00 AM	75		125	1		
1495942	12/19/2022	11:00 AM	12/21/2022	10:00 AM	75		126	1		
1495932	12/19/2022	11:00 AM	12/21/2022	10:00 AM	75		127	1		
1495993	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		208	2		
1495983	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		221	2		
1495963	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		309	3		
1495973	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		326	3		
1495953	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		410	4		
1495943	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		423	4		

Device Placement Log

1495923	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		511	5		
1495933	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		519	5	X	
1495913	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		612	6		
1495903	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		621	6		
1495902	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		705	7		
1495912	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		725	7		
1495922	12/19/2022	12:00 AM	12/21/2022	10:00 AM	75		827	8		

Appendix C

Quality Assurance Documentation

Project Quality Assurance

Quality Assurance measures were conducted in accordance with ANSI/AARST MAMF 2017, and included:

- *Duplicate* (co-located) measurement devices deployed at a rate of 10% of the measurement locations.
 - Results may not be twice or more than the co-located sample.

- *Blank* measurement devices, not exposed to indoor air, deployed at a rate of 5% of measurement locations.
 - Results may not be above the calculated lower limit of detection.
 - At a minimum of 50 test devices deployed, the number of blanks will be increased to 9, to include 3 laboratory blanks, 3 office blanks and 3 field blanks.
 - If more than 180 test devices are deployed, the blanks will be deployed at a standard rate of 5% blanks of the measurement locations.

- *Spike* measurement devices conducted at a rate of no less than 3% of sampling locations.
 - At a minimum of 100 units tested, the number of spikes increased to include 3 spiked devices from the sampling program batch to be tested and results received prior to beginning the sample deployment.

Device Location	Event Dates	Device Number	Result (pCi/L)		RPD	Device Type
Unit 8	12/19/2022 to 12/21/2022	1495960	1.1	1.0	NA	Duplicate
		1495980	0.9			
Unit 106	12/19/2022 to 12/21/2022	1495910	0.3	0.3	NA	Duplicate
		1495970	0.2			
Unit 108	12/19/2022 to 12/21/2022	1495921	0.3	0.3	NA	Duplicate
		1495931	0.3			
Unit 109	12/19/2022 to 12/21/2022	1495941	0.3	0.4	NA	Duplicate
		1495951	0.5			

Unit 105	12/19/2022 to 12/21/2022	1496342	< 0.2	NA	Field Blank
Unit 107	12/19/2022 to 12/21/2022	1495901	< 0.2	NA	Field Blank



PE Job Number: 22.24

Lot Number USUH007203

Device Range: 1495300-1497299

Chamber Info		Storage Info	
Job Number:	207825	Radon Levels:	-
Start Date:	11/12/2022	Device Numbers:	-
Stop Date:	11/14/2022	Start/Stop Date:	-
Temperature:	70.5° F	Temperature:	70-75° F
Rel. Hum:	68.10%	Rel. Hum:	30-45%

Spikes

Device	Type	Manufacture	Range	Chamber	MV	TV	IRE
1495480	LS	RaData	1495300-1497299	Bowser-Morner	33.1	38.0	-12.9%
1495534	LS	RaData	1495300-1497299	Bowser-Morner	33.5	38.0	-11.8%
1495611	LS	RaData	1495300-1497299	Bowser-Morner	37.1	38.0	-2.4%
1495999	LS	RaData	1495300-1497299	Bowser-Morner	37.7	38.0	-0.8%
1496005	LS	RaData	1495300-1497299	Bowser-Morner	35.1	38.0	-7.6%
1496278	LS	RaData	1495300-1497299	Bowser-Morner	35.3	38.0	-7.1%
1496561	LS	RaData	1495300-1497299	Bowser-Morner	35.5	38.0	-6.6%
1496655	LS	RaData	1495300-1497299	Bowser-Morner	35.9	38.0	-5.5%
1496716	LS	RaData	1495300-1497299	Bowser-Morner	34.0	38.0	-10.5%
1496924	LS	RaData	1495300-1497299	Bowser-Morner	35.8	38.0	-5.8%
1497143	LS	RaData	1495300-1497299	Bowser-Morner	36.6	38.0	-3.7%
1497255	LS	RaData	1495300-1497299	Bowser-Morner	37.3	38.0	-1.8%

IRE = Individual Relative Error; MV = Measurable Value (from lab); TV = Target Value (from chamber)

Office/Lab Transit Blanks

Device	Type	Manufacture	Range	Chamber	MV	TV	In Control
1497046	LS	RaData	1495300-1497299	Bowser-Morner	< 0.2	< 0.2	YES
1495570	LS	RaData	1495300-1497299	Bowser-Morner	< 0.2	< 0.2	YES
1495719	LS	RaData	1495300-1497299	Bowser-Morner	< 0.2	< 0.2	YES
1495955	LS	RaData	1495300-1497299	Bowser-Morner	< 0.2	< 0.2	YES
1496126	LS	RaData	1495300-1497299	Bowser-Morner	< 0.2	< 0.2	YES
1496413	LS	RaData	1495300-1497299	Bowser-Morner	< 0.2	< 0.2	YES

Winnie Cheuvront
 Manager, QA/AC - Measurement

Appendix D

Measurement Event Weather Conditions



Weather Summary

Facility: Lurie Terrace

Address: 600 West Huron, Ann Arbor, MI 48103

Placement Day: 12/19/2022

Retrieval Day: 12/21/2022

Date	Temperature (°F) Min	Temperature (°F) Max	Temperature (°F) Avg	Precipitation (Inches) Min	Precipitation (Inches) Max	Precipitation (Inches) Avg	Ground Cover (Snow/Ice inches) Min	Ground Cover (Snow/Ice inches) Max	Ground Cover (Snow/Ice inches) AVG	Wind (Speed in mph) Min	Wind (Speed in mph) Max	Wind (Speed in mph) Avg	Humidity (%) Min	Humidity (%) Max	Humidity (%) Avg
12/18/2022	23	328	26	0	0	0	0	0	0	12	21	16	72	81	76
12/19/2022	24	30	27	0	0	0	0	0	0	0	16	9	66	77	72
12/20/2022	25	34	28	0	0	0	0	0	0	0	14	6	54	78	70
12/21/2022	23	32	28	0	0	0	0	0	0	0	7	4	61	85	75
Overall Avg.	24	106	27	0	0.00	0	0	0	0	3	8	4	63	80	73

Appendix E

Professional Certification Documentation



Keith Hoylman Protect Environmental, LLC

Certified for Radon Measurement

- Certified by the National Radon Proficiency Program (NRPP)
- NRPP Certification #109193-RT
- Certified since: May 10, 2017
- Certification Expires: August 31, 2023

Certified for Radon Mitigation

- Certified by the National Radon Proficiency Program (NRPP)
- NRPP Certification #109309-RMT
- Certified since: August 2, 2017
- Certification Expires: August 31, 2023

Total NRPP Training/Education Credits: 103

- Multi-Family Measurement Certificate (MFM)
- Multi-Family Mitigation Certificate (MFMT)
- Radon Resistant New Construction Certificate (RRNC)



Kentucky

State Radon Office Contact

Clay Hardwick

Clay.hardwick@ky.gov

(502) 564-4856

Radon Office Website

American Association of Radon Scientists and Technologists (AARST)

- AARST Member ID: A5682
- Member since: May 10, 2017
- AARST Advanced Radon Measurement/Mitigation Professional (ARP)

Interested in becoming a Member of AARST?

Business Links

- [Protect Environmental, LLC Website](#)

Interested in becoming NRPP certified ?

Radon Levels in your state

Last updated on: August 13, 2021



Jimmy Rogers Protect Environmental

Certified for Radon Measurement

- Certified by the National Radon Proficiency Program (NRPP)
- NRPP Certification **#111911-RT**
- Certified since: March 1, 2021
- Certification Expires: March 31, 2023

Total NRPP Training/Education Credits: 16



Kentucky

State Radon Office Contact

Clay Hardwick

Clay.hardwick@ky.gov

(502) 564-4856

Radon Office Website

Business Links

- [Protect Environmental Website](#)

Interested in becoming a Member of
AARST?

Interested in becoming NRPP certified ?

Appendix F

EPA Radon Zone Map

Appendix G

Notification Documentation



Radon Measurement – Resident Notification (ST)

We will be conducting a radon assessment in your community. Your residence may be selected for placement of a measurement device. Access to your residence for purposes of placing and retrieving the measurement device may be necessary on the following dates:

Device Placement: **12/19/2022**

Device Retrieval: **12/21/2022**

During the measurement period, regardless of whether a measurement device is placed in your residence, you are required to maintain the following conditions to ensure a valid measurement:

- All windows must be kept closed. All exterior doors must be kept closed, except for normal entry and exit. **Windows and doors must be kept closed for a period of 12 hours prior to the device placement date and remain closed effect until the devices are retrieved.**
- Whole house fans must not be operated. Window air conditioning units may only be operated in recirculation mode. Portable window fans must be removed from the window or sealed in place.
- Fireplaces or combustion appliances, other than water heaters and cooking appliances, must not be operated unless they are your primary heat source.
- Ceiling fans, portable air filters, portable de-humidifiers, portable humidifiers or window air conditioning units operating in recirculation mode must not be operated within 20' of the measurement device.
- If a device is placed in your unit, the measurement device must not be touched, tampered with, covered, removed, or altered, and the location of the device must not be changed. Your HVAC system must be operated in the normal range – your thermostat should not be adjusted drastically, and your fan should be set in normal mode.

The technician placing and retrieving the devices is required to report any failure to maintain closed-building conditions. Failure to maintain these conditions could result in an invalid measurement and require the measurement to be repeated.

Your assistance in helping to ensure a valid measurement is greatly appreciated! Contact your management office with questions regarding this notification.

Thank you.



Radon Measurement – Responsible Party Notification (ST)

Date: December 12, 2022

Measurement Location: Lurie Terrace 600 West Huron St, Ann Arbor, MI

Measurement Period: 12/19/2022 through 12/21/2022

During the measurement period, the following conditions must be maintained in each residence (regardless of whether or not the unit contains a measurement device) and all common areas in the building to ensure a valid measurement:

- All windows must be kept closed. All exterior doors must be kept closed, except for normal entry and exit. **Windows and doors must be kept closed for a minimum period of 12 hours prior to device placement and remain closed until device retrieval.**
- Whole house fans must not be operated. Window air conditioning units may only be operated in recirculation mode. Portable window fans must be removed from the window or sealed in place.
- Fireplaces or combustion appliances, other than water heaters and cooking appliances, must not be operated unless they are the primary heat source.
- Ceiling fans, portable air filters, portable de-humidifiers, portable humidifiers or window air conditioning units operating in recirculation mode must not be operated within 20' measurement devices.
- The measurement device must not be touched, tampered with, covered, removed or altered, and the location of the device must not be changed. HVAC systems must be operated in the normal range – thermostats should not be adjusted drastically and air handlers should be set in normal mode.
- Unusual occurrences that could affect the measurement, such as power outages or extreme weather conditions, must be reported to Protect Environmental.

The technician placing and retrieving the devices is required to report any failure to maintain measurement conditions. Failure to maintain measurement conditions may result in an invalid measurement and require the measurement to be repeated.

As the responsible party for the measurement location listed above, I hereby acknowledge receipt of this Measurement Conditions Notification and agree to make reasonable efforts to ensure the conditions outlined herein are maintained throughout the measurement period.

Beth Jarock

Responsible Party