

ADDENDUM No. 2

ITB No. 4638

Gallup Park Asphalt Path Renovations

Updated Bid Due Date/Time: August 5, 2020 at 2:00 P.M. (Local Time)

The information contained herein shall take precedence over the original documents and all previous addenda (if any) and is appended thereto. **This Addendum includes six (6) pages.**

Bidder is to acknowledge receipt of this Addendum No. 2, including all attachments (if any) in its Bid by so indicating on page ITB-1 of the Invitation to Bid Form. Bids submitted without acknowledgment of receipt of this addendum may be considered nonconforming.

The following forms provided within the ITB document must be included in submitted bids:

- City of Ann Arbor Prevailing Wage Declaration of Compliance
- City of Ann Arbor Living Wage Ordinance Declaration of Compliance
- Vendor Conflict of Interest Disclosure Form
- City of Ann Arbor Non-Discrimination Ordinance Declaration of Compliance

Bids that fail to provide these forms listed above upon bid opening will be rejected as non-responsive and will not be considered for award.

I. CORRECTIONS/ADDITIONS/DELETIONS

Changes to the Bid document which are outlined below are referenced to a page or Section in which they appear conspicuously. The Bidder is to take note in its review of the documents and include these changes as they may affect work or details in other areas not specifically referenced here.

Section/Page(s)

Change

All mentions

As provided in ITB No. 4638 Bid Document:
Bid Due Date: Thursday, July 30, 2020 at 2:00 p.m.

As updated herein:
Bid Due Date: Wednesday, August 5, 2020 at 2:00 p.m.

Comment: The Due Date and Time for responses to this ITB has been extended to August 5, 2020 at 2:00 p.m. (local time). Note that all other dates are unchanged.

(this space intentionally left blank)

BF-2 – BF-5

As provided in ITB No. 4638 Bid Document:
Bid Form, Section 1 – Schedule of Prices as Page BF-2 to BF-5

As updated herein:
Bid Form, Section 1 – Schedule of Prices as Pages BF-2 to BF-5.

Comment: The intent with this change is to simply replace the inaccurate Page BF-2, BF-3, BF-4, and BF-5 provided in the ITB Document with the accurate Page BF-2, BF-3, BF-4, and BF-5 provided herein. Specifically, note the clarification to BF-2, line item 8 (Option A). Also note the addition on BF-3 of line item 25 (Option A) and the addition on BF-5 of line item 28 (Option B). Please use these updated bid forms found herein in your bid response.

II. QUESTIONS AND ANSWERS

The following Questions have been received by the City. Responses are being provided in accordance with the terms of the ITB. Bidders are directed to take note in their review of the documents of the following questions and City responses as they affect work or details in other areas not specifically referenced here.

Question 1: The depth of 21AA aggregate on BF-2, line item #8 does not match depth called out on Detail 1: Option A Shared Use Path.

Answer 1: BF-2, line item #8 has been updated to reflect Detail 1: Option A Shared Use Path.

Question 2: There is no line item on BF-2, BF-3, BF-4, or BF-5 for the concrete pad with the thickened slab called out on the Site Improvement Plan.

Answer 2: Line item #25 has been added to BF-3 and line item #28 has been added to BF-5.

Bidders are responsible for any conclusions that they may draw from the information contained in the Addendum.

PATH RENOVATION OPTION A BID ITEMS

The Bidder agrees to complete the Project and all related work, as specified for the following unit prices.

BID OPTION A: PULVERIZE EXISTING HMA IN PLACE AND INSTALL NEW HMA PATH					
Item	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
1.	General Conditions, Mobilization, Bonds, Insurance, Permits	1	LS	\$	\$
2.	Install temporary path closure fencing and tree protection fencing. Approximately 3500 Linear Feet of Tree Protection Fence	1	LS	\$	\$
3.	Installation and management of all Soil Erosion and Sedimentation Control measures. Approximately 1500 Linear Feet of silt fence.	1	LS	\$	\$
4.	Full removal of vegetation, roots, and stumps along areas to accommodate proposed work. Removed materials to be lawfully disposed off site.	1	LS	\$	\$
5.	Removal of existing benches, picnic tables, posts and concrete pads per plan. Memorial plaques on benches to be salvaged. All other removed materials to be lawfully disposed off site.	1	LS	\$	\$
6.	Pulverization of existing asphalt path surfacing (approximately 9' wide), grading and compaction for use as base aggregate. Final milling product should be no greater than 1 1/2" in diameter. Prepare and compact existing subbase of path alignment, installation of milling material to 6" depth, load, haul, place, and compact in place	2250	LF	\$	\$
7.	Excavation of existing soils and grading to widen path to 10' wide HMA and 12' wide base aggregate. Based on estimated removal of 18" depth. Excavated materials to be removed from site and lawfully disposed.	1100	SY	\$	\$
8.	Limestone for widening pathway base to 12' – 21AA, 12" depth. (Expanding path base by 4')	1100	SY	\$	\$
9.	Class II Sand Subbase for raising grade where needed	250	CYD	\$	\$

BID OPTION A: PULVERIZE EXISTING HMA IN PLACE AND INSTALL NEW HMA PATH					
Item	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
10.	Bituminous Hot Mix Asphalt Leveling course – LVSP	292	TON	\$	\$
11.	Bituminous Hot Mix Asphalt Wearing course – 5E1	292	TON	\$	\$
12.	8" x 4" Nyloplast Inline Drain	2	EA	\$	\$
13.	4" Diameter Schedule 40 PVC Drain Pipe	50	LF	\$	\$
14.	8" x 8" Nyloplast Inline Drain	2	EA	\$	\$
15.	8" Diameter Schedule 40 PVC Drain Pipe	65	LF	\$	\$
16.	Provide and install Concrete Pads for Picnic Table per standard details	2	EA	\$	\$
17.	Provide and install Picnic Tables per standard details	2	EA	\$	\$
18.	Provide and install Picnic Table in Butterfly Garden (No Concrete Pad)	1	EA	\$	\$
19.	Provide and install Concrete Pads for Benches per standard details	9	EA	\$	\$
20.	Provide and install Benches per standard details	9	EA	\$	\$
21.	Provide and Install Benches in Butterfly Garden (2) and near sculpture (3). No Concrete Pad.	5	EA	\$	\$
22.	Restoration, topsoil, seed and mulch all disturbed areas. Site Clean-up for entire project.	1	LS	\$	\$
23.	Traffic Control (Signs and Barricades)	1	LS	\$	\$
24.	Certified payroll compliance & reporting	1	LS	\$	\$
25.	Concrete Bridge Abutment	1	LS	\$	\$
Estimated Total Bid Amount (Items 1 through 25)					\$

PATH RENOVATION OPTION B BID ITEMS

The Bidder agrees to complete the Project and all related work, as specified for the following unit prices.

BID OPTION B: INSTALL NEW HMA PATH AND NEW PATH BASE					
Item	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
1.	General Conditions, Mobilization, Bonds, Insurance, Permits	1	LS	\$	\$
2.	Install temporary path closure fencing and tree protection fencing. Approximately 3500 Linear Feet of Tree Protection Fence	1	LS	\$	\$
3.	Installation and management of all Soil Erosion and Sedimentation Control measures. Approximately 1500 Linear Feet of silt fence.	1	LS	\$	\$
4.	Full removal of vegetation, roots, and stumps along areas to accommodate proposed work. Removed materials to be lawfully disposed off site.	1	LS	\$	\$
5.	Removal of existing benches, picnic tables, posts and concrete pads per plan. Memorial plaques on benches to be salvaged. All other removed materials to be lawfully disposed off site.	1	LS	\$	\$
6.	Demolition, removal, and lawful disposal of all existing asphalt paths – approximately 9' wide.	2250	LF	\$	\$
7.	Excavation, loading, hauling, and grading of existing soils to accommodate proposed 12' wide base aggregate for path Based on estimated removal of 18" depth. Excavated materials to be removed from site and lawfully disposed.	3180	SY	\$	\$
8.	Structural Geogrid placed below limestone base	3180	SY	\$	\$
9.	Limestone for pathway base – 21AA, 6" depth	3180	SY	\$	\$
10.	Class II Sand Subbase for raising grade where needed	250	CYD	\$	\$
11.	Bituminous Hot Mix Asphalt Leveling course – LVSP	292	TON	\$	\$
12.	Bituminous Hot Mix Asphalt Wearing course – 5E1	292	TON	\$	\$

BID OPTION B: INSTALL NEW HMA PATH AND NEW PATH BASE					
Item	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
13.	Undercut allowance – geotextile and 21AA Limestone compacted – Quantity based on 8” Depth	330	CY	\$	\$
14.	Undercut allowance – geotextile and 6A Limestone compacted – Quantity based on 8” Depth	330	CY	\$	\$
15.	8" x 4" Nyloplast Inline Drain	2	EA	\$	\$
16.	4" Diameter Schedule 40 PVC Drain Pipe	50	LF	\$	\$
17.	8" x 8" Nyloplast Inline Drain	2	EA	\$	\$
18.	8" Diameter Schedule 40 PVC Drain Pipe	65	LF	\$	\$
19.	Provide and install Concrete Pads for Picnic Table per standard details	2	EA	\$	\$
20.	Provide and install Picnic Tables per standard details	2	EA	\$	\$
21.	Provide and install Picnic Table in Butterfly Garden (No Concrete Pad)	1	EA	\$	\$
22.	Provide and install Concrete Pads for Benches per standard details	9	EA	\$	\$
23.	Provide and install Benches per standard details	9	EA	\$	\$
24.	Provide and Install Benches in Butterfly Garden (2) and near sculpture (3). No Concrete Pad.	5	EA	\$	\$
25.	Restoration, topsoil, seed and mulch all disturbed areas; Site Clean-up for entire project.	1	LS	\$	\$
26.	Traffic Control (Signs and Barricades)	1	LS	\$	\$
27.	Certified payroll compliance & reporting	1	LS	\$	\$
28.	Concrete Bridge Abutment	1	LS	\$	\$
Estimated Total Bid Amount (Items 1 through 28)					\$