CITY OF ANN ARBOR PUBLIC SERVICES -ENGINEERING

IN COOPERATION WITH THE UNIVERSITY OF MICHIGAN

SCHOOL GIRLS GLEN CULVERT REPLACEMENT

SHEET INDEX SHEET NO. TITLE **COVER SHEET** NOTES & LEGEND **ALIGNMENT** SURVEY, REMOVAL, & SESC MEASURES CHANNEL PLAN & PROFILE DETAILED GRADING PLAN CHANNEL DETAILS **DETAILS DETAILS** SOILS BORINGS 11 SOILS BORINGS **ACCESS PLAN** THE OMISSION OF ANY CURRENT STANDARD DETAIL DOES NOT RELIEVE THE CONTRACTOR FROM THIS REQUIREMENT. THE WORK SHALL BE PERFORMED IN COMPLETE CONFORMANCE WITH THE CURRENT PUBLIC SERVICES STANDARD SPECIFICATIONS AND DETAILS FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE

WITH PUBLIC ACT 53, THE CONTRACTOR SHALL DIAL 1-800-482-7171

THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING UTILITY OWNERS

A MINIMUM OF THREE FULL WORKING DAYS, EXCLUDING SATURDAYS,

SUNDAYS, AND HOLIDAYS PRIOR TO BEGINNING EACH EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE

WHO MAY NOT BE A PART OF THE "MISS DIG" ALERT SYSTEM.


3 WORKING DAYS

(TOLL FREE)

BEFORE YOU DIG

CALL MISS DIG


ITB No. 4689



THE	CON	STRU	CTIO	N C	OVERED	BY	THES	E PLANS	SHALL	CONF	ORM 1	ГО 1	THE	1994	EDITI	ON
OF 1	ГНЕ	CITY	OF A	ANN	ARBOR	PUB	LIC :	SERVICES	DEPAR'	TMENT	STAN	DAR	D S	PECIFI	CATIO	NS
AND	ITS	DETA	ILS	WHIC	CH ARE	INCL	UDE	D BY RE	FERENCE	.						

PERMIT		ISSUING AUTHORITY			
TRAFFIC CONTROL PERMIT		CITY OF ANN ARBOR ENGINEERING			
GRADING/SOIL EROSION & SEI CONTROL PERMIT*	DIMENTATION	CITY OF ANN ARBOR CUSTOMER SERVICE			
RIGHT-OF-WAY PERMIT*					
ACCESS AGREEMENT		CITY OF ANN ARBOR & UNIVERSITY OF MIC			
	* NO COST TO	CONTRACTOR			
CONTACT INFORMAT	TON				
PUBLIC UTILITIES		OWNER	CONTACT		
WATER			DAN WOODEN (734) 794-6350		
SANITARY	CITY OF ANN	ADDOD	TRAVIS CONLEY (734) 794-6350		
STORM	FIELD OPERAT	TIONS SERVICE UNIT R SERVICE CENTER	KEVIN SNYDER (734) 794–6350		
FORESTRY	ANN ARBOR,	SCHOOL ROAD MI 48108	MATT WALDSMITH (734) 794-6350		
SIGNS SIGNALS STREET LIGHTS			CHUCK FOJTIK (734) 794-6361		
PRIVATE UTILITIES		OWNER	CONTACT		
GAS	DTE ENERGY 3150 E. MICH YPSILANTI TO LAURIE FORR	WNSHIP, MI 48198	(734) 544-7818 (313) 389-7261		
ELECTRIC	DTE ENERGY WESTERN WAY 8001 HAGGER BELLEVILLE, M	MI 48111	(734) 397-4112 (734) 397-4303		
CABLE	COMCAST 27800 FRANK SOUTHFIELD,		(313) 999-8300		
PHONE	AT&T 550 S. MAPL ANN ARBOR,		(734) 996–2135		
FIBER OPTIC	MCI 2800 N. GLE RICHARDSON,		(972) 729-6016		

MISCELLANEOUS



CITY OF ANN ARBOR NOTES

SITE SYMBOL LEGEND

- 1. THE CONSTRUCTION COVERED BY THESE PLANS SHALL CONFORM TO THE 1994 EDITION OF THE CITY OF ANN ARBOR PUBLIC SERVICES. DEPARTMENT STANDARD SPECIFICATIONS AND ITS DETAILS WHICH ARE INCLUDED BY REFERENCE.
- THE OMISSION OF ANY CURRENT STANDARD DETAIL DOES NOT RELIEVE THE CONTRACTOR FROM THIS REQUIREMENT. THE WORK SHALL BE PERFORMED IN COMPLETE CONFORMANCE WITH THE CURRENT PUBLIC SERVICES STANDARD SPECIFICATIONS AND DETAILS.
- 3. THE LOCATION AND DEPTH OF ALL EXISTING UTILITIES AND SERVICE LEADS ARE TO BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
- 4. LOCATION AND DEPTH OF UTILITIES AS DEPICTED ON THE PLANS IS APPROXIMATE AND SHOWN ACCORDING TO THE BEST INFORMATION AVAILABLE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO EXCAVATE AHEAD AND ADJUST DEPTH OF CONFLICT UTILITIES ACCORDINGLY. ANY DAMAGE TO UTILITIES IS THE CONTRACTOR'S RESPONSIBILITY TO AVOID AND/OR REPAIR AS NECESSARY.
- DURING NON-WORKING HOURS NO TRENCH SHALL REMAIN OPEN; ANY OPEN TRENCH SHALL BE PROPERLY SECURED WITH PROTECTIVE FENCING. THIS WORK SHALL BE INCLUDED IN THE ITEM OF WORK "GENERAL CONDITIONS".
- 6. ALL LIGHT POLES, LUMINAIRES, SIGNS, FITTINGS, HYDRANTS, VALVES AND CASTINGS REMOVED DURING CONSTRUCTION ARE THE PROPERTY OF THE CITY OF ANN ARBOR. THE CONTRACTOR WITHIN 48 HOURS SHALL DELIVER TO CITY OF ANN ARBOR FIELD OPERATIONS AND MAINTENANCE FACILITY AT THE W.R. WHEELER SERVICE CENTER LOCATED AT 4251 STONE SCHOOL ROAD.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTINUOUS MAINTENANCE OF THE TEMPORARY ROAD SURFACE AND SOIL EROSION CONTROL MEASURES WITHIN THE CONSTRUCTION AREA UNTIL THE FULL COMPLETION OF THE PROJECT. THIS WORK SHALL BE INCLUDED IN THE ITEM OF WORK "GENERAL CONDITIONS".
- 8. THE LOCATION OF MATERIAL STOCK PILES AND ON-SITE STAGING AREAS TO BE APPROVED BY THE ENGINEER.
- 9. PAYMENT FOR DRAINAGE STRUCTURE SUMPS, WHERE SPECIFIED, SHALL BE INCLUDED IN THE PAYMENT FOR THE VARIOUS DRAINAGE STRUCTURE SIZES AND OR TYPES.
- 10. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THE EXISTING PUBLIC ROAD PAVEMENT. DAMAGE TO THE PUBLIC ROAD PAVEMENT DURING THE COURSE OF CONSTRUCTION MAY NECESSITATE MILLING AND RESURFACING OF THE DAMAGED AREAS PRIOR TO ACCEPTANCE, AS DIRECTED BY ENGINEERING.
- 11. DETOUR SIGNAGE THAT HAVE TWO STREET NAME PLAQUES UNDER THEM MUST HAVE A MINIMUM BOTTOM HEIGHT OF 6 FEET. THE MINIMUM SIGN BOTTOM HEIGHT FOR SIGNS IN A CURB/GUTTER AREA WITHOUT PLAQUES UNDERNEATH IS 7 FEET.

CITY OF ANN ARBOR NOTES CONTINUED

- 12. ALL TRAFFIC CONTROL DEVICES AND THEIR USAGE MUST CONFORM TO THE MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MMUTCD), LATEST EDITION.
- 13. TEMPORARY WARNING, REGULATORY, AND GUIDE SIGNS NOT REQUIRED FOR A PARTICULAR LANE OR SHOULDER CLOSURE MUST BE REMOVED, COVERED, OR LAID DOWN WITH THE LEGS REMOVED.
- 14. ANY MDOT SIGNS THAT ARE REMOVED FOR TRAFFIC CONTROL OR OBLITERATED DURING CONSTRUCTION OPERATIONS MUST BE REPLACED IN KIND ON NEW SUPPORTS.
- 15. ALL SIGN MATERIALS AND SUPPORTS MUST MEET NCHRP-350 CRASH WORTHY REQUIREMENTS

GENERAL NOTES

- 1. NOTIFY THE CITY OF ANN ARBOR ENGINEERING DIVISION A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION.
- 2. ALL CONSTRUCTION MUST BE CONFORMING TO THE CURRENT STANDARDS AND SPECIFICATIONS ADOPTED BY THE CITY OF ANN ARBOR.
- 3. CALL MISS DIG @ 800-482-7171 / 800-MISS-DIG A MINIMUM OF 72 HOURS PRIOR TO THE START OF CONSTRUCTION.
- 4. ALL SOIL EROSION AND SILT MUST BE CONTROLLED AND CONTAINED ON SITE.
- ALL EXCAVATION UNDER OR WITHIN 3 FEET OF PUBLIC PAVEMENT, EXISTING OR PROPOSED, SHALL BE BACKFILLED AND COMPACTED WITH SAND (CLASS II MDOT).
- 6. THE CONTRACTOR IS RESPONSIBLE FOR ALL DAMAGE TO EXISTING UTILITIES.
- 7. PRIOR TO THE ISSUANCE OF AN OCCUPANCY PERMIT, ENGINEERING SITE INSPECTION IS REQUIRED.

SESC NOTES

- CONSTRUCT AND MAINTAIN SOIL EROSION CONTROL MEASURES IN ACCORDANCE WITH THE PROJECT DOCUMENTS AND THE SOIL EROSION AND SEDIMENTATION CONTROL PERMIT ISSUED FOR THE PROJECT. CONTRACTOR TO OBTAIN PERMIT FROM CITY AT NO COST.
- 2. PROVIDE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES PRIOR TO STARTING DEMOLITION, EARTHWORK AND EXCAVATION. MEASURES INDICATED ON THESE DRAWINGS ARE MINIMUM REQUIREMENTS. SUPPLEMENT THESE REQUIREMENTS AS REQUIRED BY CONSTRUCTION PHASING AND SITE CONDITIONS TO
- CONTAIN SEDIMENT ON THE SITE. DO NOT ALLOW SEDIMENT TO COLLECT IN OFF SITE AREAS OR IN WATERWAYS. WATERWAYS INCLUDE NATURAL AND MANMADE OPEN DITCHES, STREAMS, STORM DRAINS,
- 4. PROVIDE AND MAINTAIN INLET FILTERS AT ALL NEW AND EXISTING CATCH BASINS AND INLET STRUCTURES WHERE IMPACTED BY CONSTRUCTION DRAINAGE UNTIL PERMANENT EROSION CONTROL MEASURES ARE IN
- 5. ENSURE SOIL AND DEBRIS FROM THE SITE REMAINS ON SITE.
- 6. INSPECT THE SOIL EROSION AND SEDIMENT CONTROL MEASURES ONCE EACH WEEK AND WITHIN TWENTY-FOUR (24) HOURS OF A PRECIPITATION EVENT WHICH RESULTS IN A STORM WATER DISCHARGE FROM THE SITE. A LOG OF INSPECTION REPORTS SHALL BE MAINTAINED AND ACCESSIBLE IN ACCORDANCE WITH NPDES REQUIREMENTS.
- 7. PROVIDE AND MAINTAIN SILT FENCE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. MAINTENANCE INCLUDES THE REMOVAL OF BUILT-UP SEDIMENT WHEN THE SEDIMENT ACCUMULATES TO 1/3 OF THE HEIGHT OF THE SILT FENCE. REMOVE, REPLACE, RETRENCH, OR RE-BACKFILL THE SILT FENCE IF IT FAILS. REINSTALL FENCE DAMAGED BY CONSTRUCTION OR WEATHER AT NO ADDITIONAL COST TO THE OWNER.
- 8. PROVIDE AND MAINTAIN INLET FILTERS IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. MAINTENANCE CONSISTS OF REMOVING ALL SEDIMENT WITH A STIFF BRISTLE BROOM OR SQUARE POINT SHOVEL. IF THE INLET FILTER IS DAMAGED, REPLACE BOTH THE STONE AND GEOTEXTILE FILTER FABRIC.
- PREPARE SEED BEDS AND SOW SEED IN ACCORDANCE WITH THE SEED SUPPLIER'S RECOMMENDATIONS. FOLLOW SPECIAL PROVISION FOR TURF ESTABLISHMENT.
- 10. MAINTAIN DUST CONTROL DURING CONSTRUCTION. WATER TANK TRUCKS SHALL BE USED ON HAUL ROAD, ON-SITE DISTURBED AREAS, OR OTHER PLACES WHERE DUST BECOMES A PROBLEM. THIS WORK IS INCLUDED IN PAYMENT FOR ROADWAY GRADING.
- 11. PROMPTLY REMOVE ALL MUD, DIRT AND DEBRIS TRACKED ONTO EXISTING ROADS FROM THE SITE.
- 12. ALL SEEDING SHALL BE SEED MIXTURE THM.

PROPOSED UTILITIES

(832.56)

8" SAN. ___ SANITARY SEWER & MANHOLE

MAX. FI EVATION OF LOT


LEAD AT PROPERTY LINE


CATCH BASIN

REMOVAL NOTES

- THE EXTENT OF REMOVALS AND DEMOLITION SHALL BE FIELD VERIFIED BY CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION. NOTIFY ENGINEER OF ANY DEVIATIONS FROM INFORMATION SHOWN.
- PRIOR TO CONSTRUCTION ALL FENCING, BARRICADES, ENCLOSURES, ETC., MUST BE INSTALLED AND APPROVED BY OWNER OR CONSTRUCTION MANAGER.
- DISPOSE OF DEMOLITION AND EXCAVATION MATERIALS IN ACCORDANCE WITH CONTRACT
- 4. SOIL EROSION AND SEDIMENTATION CONTROL MEASURES MUST BE IN PLACE PRIOR TO
- UNLESS SPECIFICALLY NOTED FOR REMOVAL ON THE PLANS, ALL SIDEWALKS, DRIVES, CULVERTS, DRAINAGE STRUCTURES, AND ABOVE AS WELL AS BELOW GRADE UTILITIES SHALL BE PROTECTED. ALL SUCH ITEMS DAMAGED OR DESTROYED DURING CONSTRUCTION SHALL BE REMOVED AND REPLACED WITH NEW AT NO ADDITIONAL COST
- PROTECT EXISTING TREES TO REMAIN WITH TEMPORARY FENCING AT THE DRIP LINE. NO GROUND DISTURBANCE OR STORAGE OF MATERIAL/EQUIPMENT SHALL OCCUR WITHIN
- NEEDING TO BE REMOVED OR RELOCATED SHALL BE COORDINATED WITH THE AFFECTED UTILITY COMPANY. ADEQUATE TIME SHALL BE PROVIDED FOR RELOCATION AND CLOSE COORDINATION WITH THE UTILITY COMPANY IS NECESSARY TO PROVIDE A SMOOTH TRANSITION IN UTILITY SERVICE. PAY CLOSE ATTENTION TO EXISTING UTILITIES WITHIN THE CONSTRUCTION LIMITS. GIVE NOTICE TO ALL UTILITY COMPANIES REGARDING DESTRUCTION AND REMOVAL OF ALL SERVICE LINES AND CAP ALL LINES BEFORE PROCEEDING WITH THE WORK.
- 8. PERFORM CLEARING, GRUBBING, TREE AND STUMP REMOVAL, TOPSOIL REMOVAL AND
- BEEN INSTALLED. TESTED AND IS OPERATIONAL.
- THE LOCATIONS OF ALL EXISTING UTILITIES SHOWN ON THIS DRAWING HAVE BEEN DETERMINED FROM THE BEST INFORMATION AVAILABLE AND ARE GIVEN FOR THE CONVENIENCE OF THE CONTRACTOR. VERIFY CRITICAL INVERT INFORMATION PRIOR TO BEGINNING CONSTRUCTION.
- SHALL BE SAWCUT AND REPLACED AT NO ADDITIONAL COST TO THE OWNER.
- 12. COORDINATE SEQUENCING AND PHASING OF DEMOLITION WITH CONSTRUCTION MANAGER.

- SOIL EROSION CONTROL MEASURES





EXISTING UTILITIES _____ SANITARY SEWER & MANHOLE 12" STM. _ ______ STORM SEWER & MANHOLE CATCH BASIN CURB TYPE CATCH BASIN LAWN TYPE HYDRANT PLUG _____6" WTR. WATER MAIN

_____ <u>4" FM</u> FORCE MAIN ____ _ UNDERGROUND ELECTRIC

______6" STEAM UNDERGROUND STEAM ______2" SPRK.__ UNDERGROUND SPRINKLER

_____ _ _ _ CATV CABLE TELEVISION TELEPHONE PEDESTAL PIPE-ONLY CULVERT $\Box = \Box$

FLARED END SECTION CULVERT HEADWALL CULVERT

STANDARD FIRE HYDRANT ASSEMBLY

STANDARD SEWER CLEAN OUT — TEMPORARY MEASURE - PERMANENT MEASURE ____ STORM SEWER & MANHOLE SECTION C2 / SCALE: SCALE OF SECTION

P.

SECTION IS DRAWN ON

MISCELLANEOUS

SOIL EROSION CONTROL

DETAIL C2 SCALE: SCALE OF DETAIL SHEET NUMBER
DETAIL IS DRAWN ON

855.50 TC PROPOSED TOP OF CURB ELEVATION 855.00 TP 855.00 TW PROPOSED TOP OF WALL ELEVATION 855.00 EW PROPOSED EDGE OF WALK ELEVATION 855.00 FF 855.00 EM PROPOSED HIGH POINT ELEVATION 855.00 HP 855.00 LP PROPOSED LOW POINT ELEVATION

PROPOSED TOP OF PAVEMENT ELEVATION PROPOSED FINISHED FLOOR ELEVATION PROPOSED EDGE OF METAL ELEVATION

ALL SYMBOLS MAY NOT APPEAR ON DRAWINGS.

FORCE MAIN AIR RELEASE STRUCTURE TELEPHONE LINE PIPE-ONLY CULVERT FLARED END SECTION CULVERT

STARTING REMOVALS AND DEMOLITION. TO THE OWNER.

THE DRIP LINE LIMITS.

ELECTRICAL, TELEPHONE, CABLE TV, WATER, FIBER OPTIC CABLE AND/OR GAS LINES

STOCKPILING IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

BEFORE REMOVING OR ABANDONING ANY UTILITY PIPES, VERIFY NEW UTILITY PIPE HAS

- 11. DAMAGE CAUSED TO SURROUNDING AREA PAVEMENT OUTSIDE THE CONSTRUCTION LIMITS
- 13. SEE OTHER DRAWINGS FOR ADDITIONAL SITE DEMOLITION WORK.
- 14. SAWCUT CURB AND GUTTER AND SIDEWALKS TO NEAREST JOINT.

SITE PLAN ABBREVIATIONS

IIE PL	AN ABBREVIATIO	INO	
BBREV.	MEANING	ABBREV.	MEANING
ABAN.	ABANDON	MDNR	MICHIGAN DEPARTMENT OF NATURAL RESOURCES
ADJ.	ADJACENT	MDOT	MICHIGAN DEPARTMENT OF TRANSPORTATION
AGG.	AGGREGATE	MDPH	MICHIGAN DEPARTMENT OF PUBLIC HEALTH
ALT.	ALTERNATE	MFGR	MANUFACTURER
APPD.	APPROVED	MGD	MILLION GALLONS PER DAY
	APPROXIMATE	MH.	MANHOLE
B/B	BACK TO BACK	MIN.	MINIMUM
BIT.	BITUMINOUS	MISC.	MISCELLANEOUS
BLDG. BLVD.	BUILDING BOULEVARD	MJ MON.	MECHANICAL JOINT
BM	BENCH MARK	NA	MONUMENT NOT APPLICABLE
BNDY.	BOUNDARY	NIC	NOT IN CONTRACT
BOT.	BOTTOM	NRCP	NON-REINFORCED CONCRETE PIPE
BSMT.	BASEMENT	NTS	NOT TO SCALE
C & G	CURB AND GUTTER	OC	ON CENTER
C/C	CENTER TO CENTER	OD	OUTSIDE DIAMETER
CATV	CABLE TELEVISION	OE	OVERHEAD ELECTRIC
CB	CATCH BASIN	OP	FIBER OPTICS
CF	CUBIC FEET	ORIG.	ORIGINAL
CFS	CUBIC FEET PER SECOND	OT	OVERHEAD TELEPHONE
CL	CENTERLINE	PC	POINT OF CURVE
CMP	CORRUGATED METAL PIPE	PCC	POINT OF COMPOUND CURVATURE
CO.	CLEAN OUT	PE DEDE	POLYETHYLENE
CONC.	CONCRETE		POLYETHYLENE PIPE PERFORATED
CONST.	CONSTRUCTION	PERF.	
COORD. CP	COORDINATE COPPER PIPE	PI PIV	POINT OF INTERSECTION POST INDICATOR VALVE
CSP	CORRUGATED STEEL PIPE	PL	PROPERTY LINE
CSPA	CORRUGATED STEEL PIPE ARCH	POB	POINT OF BEGINNING
CULV.	CULVERT	POE	POINT OF ENDING
CY	CUBIC YARD	PRC	POINT OF REVERSE CURVE
DEG (°)	DEGREE	PROP.	PROPOSED
DEMO.	DEMOLISH	PSF	POUNDS PER SQUARE FOOT
DIP	DUCTILE IRON	PSI	POUNDS PER SQUARE INCH
DIA.	DIAMETER	PT	POINT OF TANGENCY
DIM.	DIMENSION	PVC	POLYVINAL CHLORIDE
DIST.	DISTANCE	PVC	POINT OF VERTICAL CURVE
ELEC	ELECTRIC CONDUIT	PVI	POINT OF VERTICAL INTERSECTION
EL.	ELEVATION	PVMT.	PAVEMENT PANAL TANGENGY
ENGR. EOM	ENGINEER	PVT	POINT OF VERTICAL TANGENCY QUANTITY
EQUIP.	EDGE OF METAL EQUIPMENT	QTY. R.	RADIUS
ESMT.	EASEMENT	RCP	REINFORCED CONCRETE PIPE
EXIST. EX.	EXISTING	RED.	REDUCER
EXT.	EXTERIOR	REF.	REFERENCE
F/F	FACE TO FACE	REQD.	REQUIRED
FDN.	FOUNDATION	REV.	REVISION
FIG.	FIGURE	RJ	RESTRAINED JOINT
FF	FINISH FLOOR	ROW	RIGHT OF WAY
FIN. GR.	FINISH GRADE	SAN	SANITARY SEWER
FM	FORCE MAIN	SF	SQUARE FOOT
FTG.	FOOTING	SPEC.	SPECIFICATION
GEN.	GENERATOR	SS	SIDE SLOPE
GND.	GROUND	STA.	STATION
GPD	GALLONS PER MINITE	STD.	STANDARD
GPM	GALLONS PER MINUTE	STL. STM	STEEL STORM SEWER
HDPE HDWL.	HIGH DENSITY POLYETHELENE HEADWALL	SYD	STORM SEWER SQUARE YARD
H.	HEIGHT	TC	TOP OF CURB
HORIZ.	HORIZONTAL	TAN.	TANGENT
. = : :· = :			· - ···




OF ANN ARBOR
GLEN CULVERT RE
NICHOLS DRIVE
NOTES

P -ENGINEERING -

SERVICES-

PUBLIC S







BENCH MARK G ELEVATION: 779.28
CHISELED SQUARE ON NORTHEASTERLY CORNER OF CONCRETE
SANITARY VAULT ON WEST SIDE OF CREEK.

BENCH MARK H ELEVATION: 766.37
MAG SPIKE ON NORTHERLY SIDE OF 18" DECIDIOUS TREE ON SOUTH SIDE OF NICHOLS DRIVE AND ± 100' EAST OF CREEK.

CHE	DRAWN CHE	DATE	DESCRIPTION
		08-11-2021	BIDS



0+12.17 | 285882.74 | 13297090.79

0+27.94 | 285898.40 | 13297092.70

0+34.01 | 285901.77 | 13297097.74

0+38.98 | 285902.93 | 13297102.57

0+43.56 | 285903.70 | 13297107.08 |

NICHOLS DRIVE ALIGNMENT

SCALE: 1" = 10'

PUBLIC SERVICES-ENGINEERING - CITY OF ANN ARBOR

SCALE PLAN:


SCALE PLAN:


SCALE PLAN:


SCHOOL GIRLS GLEN CULVERT REPLA

NICHOLS DRIVE

ALIGNMENT





















ELEVATION (NORTH END SHOWN, SOUTH END SIMILAR)





STREAM FLOW DATA					
FLOOD FREQUENCY	PEAK DISCHARGE (CFS)				
10% (10-YR, 24-HR)	27				
2% (50-YR, 24-HR)	57				
1% (100-YR, 24-HR)	73				

S GLEN CULVERT RE NICHOLS DRIVE DETAILS SERVICES-ENGINEERING
SCHOOL

SHEET No.

NICHOLS DRIVE CULVERT DETAILS







SCHOOLGIRLS' GLEN CASCADING ROCK CHANNEL DETAIL

FIELD STONE QUANTITY ESTIMATE INCLUDED IN THE CASCADING ROCK CHANNEL ESTIMATES


0 5 10 VERT. SCALE: 1" = 10'







FIELDSTONE SPILLWAY AND FIELDSTONE
WEIR STABILIZATION DETAILS

ESTIMATE 4 CY 8" TO 16" FIELDSTONE





ESTIMATE 23 CY 8" TO 12" FIELDSTONE



SCHOOL GIRLS' GLEN
PLUNGE POOL COMPLEX DETAILS

NO SCALE

PUBLIC SERVICES-ENGINEERING - CITY OF ANN ARBOR

SALE PLAN:

SCHOOL GIRLS GLEN CULVERT REPLACEMENT
NICHOLS DRIVE

DETAILS

DETAILS

-TAPERED HOLES PERMITTED

OPTIONAL RECESS DETAIL

BOX CULVERT

TIE HOLE LOCATION

JOINT TIE ASSEMBLIES ARE LOCATED ON THE SIDES OF CULVERTS ONLY. JOINT TIE ASSEMBLIES TO BE USED TO ONLY HOLD CULVERT SECTIONS TOGETHER. NOT FOR PULLING SECTIONS TIGHT.

MICHIGAN DEPARTMENT OF TRANSPORTATION

BURGAL OF DEVELOPMENT STANDARD PLAN FOR


BOX CULVERT

JOINT TIE ASSEMBLIES

R-84-A

FILL ENTIRE AMBULAR SPACE WITH HOLE SEALANT (TYP) -











OF ANN ARBOR
S GLEN CULVERT RE
NICHOLS DRIVE
DETAILS

SERVICES-ENGINEERING
SCHOOL

PUBLIC SCALE PLAN:

SHEET No.






CHANNEL PROFILE

APRON

- NONWOVEN

GEOTEXTILE



—2" TO 3" STONE (TYP.)

GEOTEXTILE 6"


AGGREGATE LAYER

— WASHED

NOTES:


TOP OF BANK -

- 1. PLACE NONWOVEN GEOTEXTILE, MATERIALS, UNDER THE BOTTOM AND SIDES OF THE DAM PRIOR TO PLACEMENT OF STONE. CONSTRUCT THE CHECK DAM WITH WASHED STONE OR EQUIVALENT RECYCLED CONCRETE (WITHOUT REBAR) WITH SIDE SLOPES OF 2:1 OR FLATTER AND A MINIMUM TOP WIDTH OF 12 INCHES, PLACE THE STONE SO THAT IT COMPLETELY COVERS THE WIDTH OF THE CHANNEL AND CHANNEL BANKS, FORM THE WEIR SO THAT TOP OF THE OUTLET CREST IS APPROXIMATELY 6 INCHES LOWER THAN THE OUTER EDGES. LINE THE UPSTREAM FACE OF THE DAM WITH WASHED AGGREGATE (¾ TO 1½ INCH).
- 2. SET THE HEIGHT FOR THE WEIR CREST EQUAL TO ONE—HALF THE DEPTH OF THE CHANNEL OR DITCH. TO AVOID SCOUR THE MAXIMUM HEIGHT OF THE WEIR CREST MUST NOT EXCEED 2.0 FEET. CHECK DAMES SHOULD BE INSPECTED BEFORE/AFTER HEAVY RAIN EVENTS. CLOGGED STONE SHOULD BE PERIODICALLY CLEANED.
- 3. REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES ONE-HALF OF THE HEIGHT OF THE WEIR CREST. MAINTAIN LINE, GRADE, AND CROSS SECTION. CLOGGED STONE SHOULD BE PERIODICALLY CLEANED.




- 1. CONSTRUCT SILT FENCE BEFORE UPSLOPE GROUND COVER IS REMOVED. CLEARING, GRUBBING, AND STUMPING CAN OCCUR BEFORE SILT FENCE INSTALLATION IF GROUND COVER IS NOT REMOVED.
- 2. PLACE ALL SILT FENCE PARALLEL TO THE SLOPE AS POSSIBLE SO THAT WATER WILL NOT CONCENTRATE AT LOW POINTS IN THE FENCE AND SO THAT SMALL SWALES OR DEPRESSIONS THAT MAY CARRY SMALL CONCENTRATED FLOWS TO THE SILT FENCE ARE DISSIPATED ALONG ITS LENGTH.
- 3. INSTALL ENDS OF THE SILT FENCES UPSLOPE 12" IN ELEVATION SO THAT WATER PONDED BY THE SILT FENCE WILL BE PREVENTED FROM FLOWING AROUND THE ENDS.
- 4. INSTALL THE TRENCH WITH A TRENCHER, CABLE LAYING MACHINE, SLICING MACHINE, OR OTHER SUITABLE DEVICE THAT WILL ENSURE AN ADEQUATELY UNIFORM TRENCH DEPTH.
- 5. WHERE TWO SECTIONS OF PREFABRICATED SILT FENCE ARE COMBINED INTO ONE RUN, THE END POSTS SHALL BE CONNECTED TOGETHER, NOT SIMPLY OVERLAPPED.
- 6. SILT FENCE SHALL ALLOW RUNOFF TO PASS ONLY AS DIFFUSE FLOW THROUGH THE GEOTEXTILE. IF RUNOFF OVERTOPS THE SILT FENCE, FLOWS AROUND THE ENDS, OR IN ANY OTHER WAY BECOMES A CONCENTRATED FLOW, ONE OF THE FOLLOWING SHALL BE PERFORMED, AS APPROPRIATE: A) AN ADDITIONAL RUN OF SILT FENCE SHALL BE PLACED UPSTREAM, B) THE LAYOUT OF THE SILT FENCE SHALL BE CHANGED, C) ACCUMULATED SEDIMENT SHALL BE REMOVED, OR D) OTHER BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED.
- 7. INSPECT FREQUENTLY AND IMMEDIATELY AFTER EACH STORM EVENT. CHECK SEVERAL TIMES DURING PROLONGED STORM EVENTS. IF NECESSARY, REPAIR IMMEDIATELY.
- 8. REMOVE SEDIMENT DEPOSITS WHEN THE DEPOSIT REACHES APPROXIMATELY ONE-HALF OF THE HEIGHT OF THE SILT FENCE.
- 9. REMOVE SILT FENCE ONLY WHEN ALL UPSTREAM VEGETATION IS FULLY ESTABLISHED AND DIRECTED BY ENGINEER/OWNER.









DEPARTMENT CIRECTOR

Paul C. Augen

DESIGN DIVISION

CHECKED BY: M.K.F.

Gregg Brunner, P.E. Georg Brunner Jul 24 2019 11:24 AM

- SEE DETAIL A

1" DIA. TIE ROD -

FILL ENTIRE ANNULAR SPACE WITH HOLE SEALANT PER CURRENT SPECIFICATIONS (TYP)

TAPERED HOLES PERMITTED -

— AGGREGATE COURSE SURFACE, 8 INCH

TYPICAL GRAVEL ROAD CROSS SECTION NO SCALE

* Visual estimate following ASTM D 2488 unless laboratory testing has been performed. Stratification changes are approximated between samples.

Visual estimate following ASTM D 2488 unless laboratory testing has been performed. Stratification changes are approximated between samples.

OF ANN ARBOR
GLEN CULVERT RE
NICHOLS DRIVE
SOIL BORING

P -ENGINEERING -

SERVICES-E PUBLIC SCALE PLAN:

SHEET No.

10

* Visual estimate following ASTM D 2488 unless laboratory testing has been performed. Stratification changes are approximated between samples.

Project: Schoolgirl's Glen - Nichols Drive Culvert F. Client: Fishbeck Location: Ann Arbor, Michigan Drill Type: Hand Auger Crew Chief: Field Eng.: JS Re Coordinates: N=285956.8 E=13297138.6 (MI South Elevation: 761.0 ft Datum: NAVD 88 (GPS Ob Notes: Plugging Record: Backfilled borehole with compacted Component Percentages: Trace < 5%, Few 5-10%, Little 15 Elev. Depth Sample Recov. Dyn. Cone "USCS FT. FT. Number FT. Eq. "N": Group ASTM STP 399 Symbol 760.8 0.25 760.5 0.50	Date Begin: 02/23/2021 Tooling Type Casing ev. By: RW Sampler Hand August Core Tube SPT Hammer ed cuttings. Depth Drilled: 0.5 ft. 5-25%, Some 30-45%, Mostly 50-100%	Dia. Groundwater, ft. During None	Project: Schoolgirl's Glen - Nichols Drive Culver Client: Fishbeck Location: Ann Arbor, Michigan Drill Type: Hand Auger Crew Chief: Field Eng.: JS Coordinates: N=285951.8 E=13297138.6 (MI Sou Elevation: 761.0 ft Datum: NAVD 88 (GPS 6 Notes: Plugging Record: Backfilled borehole with compact Component Percentages: Trace < 5%, Few 5-10%, Little Elev. Depth Sample Recov. Dyn. Cone *USC: FT. FT. Number FT. Eq. *N": Group ASTM STP 399 Symbol 760.8 0.25 760.5 0.50 GP	Date Begin: 02/23/2021 Tooling Type Casing Rev. By: RW Sampler Hand Au th iff) Core Tube SPT Hammer SPT Hammer Sted cuttings. Depth Drilled: 0.5 ft. 15-25%, Some 30-45%, Mostly 50-100% S Brown gray poorly graded GRAVEL with	Dia. Groundwater, ft. During None	Project: Schoolgirl's Glen - Nichols Drive Culve Client: Fishbeck Location: Ann Arbor, Michigan Drill Type: Hand Auger Crew Chief: Field Eng.: JS Coordinates: N=286006.3 E=13297156.1 (MI Science Elevation: 754.6 ft Datum: NAVD 88 (GPS Notes: Plugging Record: Backfilled borehole with comparation of the component Percentages: Trace < 5%, Few 5-10%, Little Elev. Depth Sample Recov. Dyn. Cone *US FT. FT. Number FT. Eq. "N": Grog ASTM STP 399 Sym 754.4 0.25 754.1 0.50 A-1 5 753.9 0.75 753.6 1.00 752.9 1.75 752.6 2.00 752.4 2.25 752.1 2.50 A-2 8	Date Begin: 02/24/202 Tooling Type Casing Rev. By: RW Sampler Hand Are Core Sobservation) Tube SPT Hammer acted cuttings. Depth Drilled: 3.0 ft. Side 15-25%, Some 30-45%, Mostly 50-100% SCS Soup *DESCRIPTION	e Dia. Groundwater, ft. During Nor
Project: Schoolgirl's Glen - Nichols Drive Culvert F. Client: Fishbeck Location: Ann Arbor, Michigan Drill Type: Hand Auger Crew Chief: Field Eng.: JS Re Coordinates: N=285984.9 E=13297162.8 (MI South Elevation: 755.9 ft Datum: NAVD 88 (GPS Ob Notes: Plugging Record: Backfilled borehole with compacted of the component Percentages: Trace < 5%, Few 5-10%, Little 15 Elev. Depth Sample Recov. Dyn. Cone "USCS FT. FT. Number FT. ASTM STP 399 Symbol 755.7 0.25 755.4 0.50 A-1 7 755.2 0.75 754.9 1.00 754.7 1.25 754.4 1.50 755.2 2.75 A-2 9 753.4 2.50 753.2 2.75	Date Begin: 02/24/2021 Tooling Type Casing Sampler Hand Aug Core Tube SPT Hammer Depth Drilled: 2.8 ft. 5-25%, Some 30-45%, Mostly 50-100% *DESCRIPTION Sandy Topsoil with occsaional roots and few coarse to fine gravel End of Boring End of Boring	Project No.: 201675 Boring No.: B-6 Sheet: 1 of 1 Date End: 02/24/2021 Dia. Groundwater, ft. During None Jer 3 1/4" Seepage Date Depth, ft. QP Calibrated Penetrometer (tons/sq. ft.) Test % pcf Auger refusal at 2.8' due to possible coarse gravel / COBBLE	Project: Schoolgirl's Glen - Nichols Drive Culver Client: Fishbeck Location: Ann Arbor, Michigan Drill Type: Hand Auger	Rev. By: RW th ift) Observation) Tube SPT Hammer SPT Hammer Depth Drilled: 3.5 ft. 15-25%, Some 30-45%, Mostly 50-100% Tube SPT Hammer T	Project No.: 201675 Boring No.: B-7 Sheet: 1 of 1 Date End: 02/24/2021 Dia. Groundwater, ft. During None Inger 3 1/4" End NA Seepage Depth, ft. QP = Calibrated Penetrometer (tons/sq. ft.) QP MST DD REMARKS 1.5 Auger refusal at 3.5' due to possible coarse gravel / COBBLE	Project: Schoolgirl's Glen - Nichols Drive Culvic Client: Fishbeck Location: Ann Arbor, Michigan Drill Type: Hand Auger Crew Chief: Field Eng.: JS Coordinates: N=285961.2 E=13297128.7 (MI Science Schools) Elevation: 765.2 ft Datum: NAVD 88 (GPS Notes: Plugging Record: Backfilled borehole with compact Percentages: Trace < 5%, Few 5-10%, Little Elev. Depth Sample Recov. Dyn. Cone "US FT. FT. Number FT. Eq. "N": Gro ASTM STP 399 Sym 765.0 0.25 764.7 0.50 A-1 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	Rev. By: RW puth ift) S Observation) acted cuttings. Depth Drilled: 3.0 ft. Depth Drilled: 3.0 ft.	Project No.: 201675 Boring No.: B-8 Sheet: 1 of 1 1 Date End: 02/24/2021 e Dia. Groundwater, ft. During Nor uger 3 1/4" End N/ Seepage Date Depth QP = Calibrated Penetrometer (tons tsf % pcf REMARKS 1.5 Auger refusal at 3.0' possible coarse grav COBBLE

* Visual estimate following ASTM D 2488 unless laboratory testing has been performed. Stratification changes are approximated between samples.

* Visual estimate following ASTM D 2488 unless laboratory testing has been performed. Stratification changes are approximated between samples.

* Visual estimate following ASTM D 2488 unless laboratory testing has been performed. Stratification changes are approximated between samples.

			Kno	3
				DRAWN CHECKED
				DRAWN
			08-11-2021	DATE
			BIDS	DESCRIPTION
				REV.
BOR	ZEET	-8647		


PUBLIC SERVICES-ENGINEERING - CITY OF ANN ARBOR


SCALE PLAN:

SCHOOL GIRLS GLEN CULVERT REPL


BRAWING No.


SOIL BORINGS





STORAGE LOT ACCESS






	feet
Width	: 8.00
Track	: 8.00
Lock to Lock Time	: 6.0

Steering Angle

: 31.8





1. CONTRACTOR PARKING IN ARBORETUM MUST BE APPROVED BY THE ARBORETUM PERSONNEL. 2. ACCESS INTO THE ARBORETUM IS LIMITED TO THE LOCATIONS SHOWN.

4. CONTRACTOR MUST UTILIZE SMALL, FLATBED TRUCKS TO DELIVER CULVERT PIECES TO THE SITE BY STORING BOX PIECES AT THE 721 N MAIN STREET PARKING LOT THEN RELOADING ONTO SMALLER WHEELBASE VEHICLES FOR DELIVERY TO THE SITE, OR OTHER SUITABLE METHOD APPROVED BY THE ENGINEER.


SNOW, ICE OR OTHER MATERIAL TO SAFELY ACCESS AND USE THE PARKING LOT. ALL WORK REQUIRED TO ACCESS, USE AND MAINTAIN THE PARKING LOT WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE ITEM OF WORK FOR "GENERAL CONDITIONS".

THE ALLOWABLE AREA.

TOWED AT OWNER'S EXPENSE.

8. CONTRACTOR TO ACCESS NICHOLS DRIVE THROUGH E MEDICAL DRIVE

1. ALL TRAFFIC CONTROL DEVICES SHALL COMPLY WITH MMUTCD TYPICAL M0231a, AS APPLICABLE



TRUCK TURN DETAIL

NOTES

ANY QUESTIONS REGARDING ACCESS TO OR USE OF THE SITE SHALL BE SUBMITTED TO THE ENGINEER IN WRITING PRIOR TO THE CONTRACTOR TAKING ANY ACTION CONTRADICTORY TO THESE PLANS. 3. THE PRE-PROPOSAL MEETING AND WALK-THROUGH FOR THIS PROJECT IS MANDATORY.

5. THE PARKING LOT AT 721 N MAIN STREET MIGHT NOT BE MAINTAINED DURING THE WINTER MONTHS. THE CONTRACTOR MAY NEED TO REMOVE

6. CONTRACTOR SHALL BE ALLOWED TO UTILIZE THE PARKING LOT AT 721 N MAIN STREET FOR EMPLOYEE PARKING. THE CITY WILL DETERMINE

7. CONTRACTOR EMPLOYEE PARKING ON NICHOLS DRIVE OUTSIDE OF THE CONSTRUCTION AREA IS STRICTLY PROHIBITED. VEHICLES MAY BE

MOT NOTES

2. ALL NON-APPLICABLE SIGNAGE WITHIN THE CONSTRUCTION INFLUENCE AREA SHALL BE MODIFIED TO FIT CONDITIONS, COVERED, OR REMOVED.



E MEDICAL CENTER TO NICHOLS DR

OF ANN ARBOR
GLEN CULVERT RE
NICHOLS DRIVE
ACCESS PLAN 의 명

SERVICES-ENGINEERING
SCHOOL