

ADDENDUM No. 2
ITB 4267, Arbor Oaks Park Rain Garden
City of Ann Arbor
Due: Wednesday, May 15, 2013 at 10:00 a.m.

The following changes, additions, and/or deletions shall be made to the Invitation to Bid for the Arbor Oaks Park Rain Garden, ITB No. 4267, on which bids will be received on or before 10:00 A.M. Wednesday, May 15, 2013.

The information contained herein shall take precedence over the original documents and all previous addenda, and is appended thereto. This Addendum includes 3 pages, and no drawings.

Changes in the Invitation to Bid which are outlined below are referenced to a page or attachment in which they appear conspicuously. The Bidder is to take note in its review of the documents and include these changes as they affect work or details in other areas not specifically referenced here.

Item #1: Detailed Specifications: 31 10 00 Site Preparation – Add the following to Part 3.01 (Protection of Persons and Property):

G. Public access to Arbor Oaks Park shall be maintained at all times during construction. A minimum of 2 points of access shall be maintained as open entries at any time. The Contractor shall submit a public access and safety plan at the pre-construction meeting. The work cannot start until the public access and safety plan is approved by the Owner. The Contractor shall be responsible for determining how to manage public access and safety in accordance with their work plan. All access points, whether open or temporarily closed, shall be signed at all times and indicate which access points are open or closed.

Bidders are required to acknowledge receipt of this Addendum No. 2 when submitting its Bid.

Bidders shall attach this Addendum to their proposal and shall enter Addendum Number and date on the Bid Form, and shall sign the Addendum and submit same with bid. Failure to include signed Addendum with bid proposal shall be cause for rejection of bid. Bidders shall affix the signed Addendum and the revised Bid Form to the inside cover of the bid Specification.

Authorized Signature

Date

Print Name:

Title:

SECTION 31 10 00 SITE PREPARATION

PART 3 - EXECUTION

3.01 PROTECTION OF PERSONS AND PROPERTY

- A. Construction Fence shall be installed as indicated on the plans and in addition any area where the CONTRACTOR feels it is necessary to protect vegetation, structures, private properties, or secure construction and hazardous areas. Additional fence beyond what is indicated on the plans shall be done at the CONTRACTOR'S expense.
- B. Construction fence shall be installed per manufactures standards and specifications.
- C. Protect structures, trails, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and other hazards created by all construction operations.
- D. Use means necessary to protect persons and property as required by local and state governing authorities including traffic warning devices when working in Right-Of-Way.
- E. Provide safe visitor crossing as indicated on the plans. Meet with OWNER to coordinate needs, hours and location of traffic control measures and staffing.
- F. Maintain access to the site at all times. Protect Benchmarks from damage or displacement. Locate, identify and protect utilities that remain from damage. Protect trees, wetlands, plant growth and features designated to remain as final landscaping.
- G. Public access to Arbor Oaks Park shall be maintained at all times during construction. A minimum of 2 points of access shall be maintained as open entries at any time. The Contractor shall submit a public access and safety plan at the pre-construction meeting. The work cannot start until the public access and safety plan is approved by the Owner. The Contractor shall be responsible for determining how to manage public access and safety in accordance with their work plan. All access points, whether open or temporarily closed, shall be signed at all times and indicate which access points are open or closed.