

ADDENDUM NO. 1  
TO  
CONTRACT DOCUMENTS  
FOR  
BELMONT SANITARY SEWER EXTENSION PROJECT  
FOR THE  
CITY OF ANN ARBOR, MICHIGAN

The following changes, additions, and/or deletions shall be made to the Contract Documents for the Belmont Sanitary Sewer Extension Project for the City of Ann Arbor, Michigan, Bid No. ITB-4299 on which proposals will be received on, or before 2:00 P.M., Friday, August 9, 2013.

The information contained herein shall take precedence over the original documents and all previous addenda and is appended thereto. This Addendum includes 3 pages.

**The Contractor is to acknowledge receipt of this Addendum No. 1 on page ITB-1 of the Contract Documents prior to submitting its Proposal.**

1. Changes in the Contract Documents

Changes in the Contract Documents which are outlined below are referenced to a page or in which they appear conspicuously. The bidder is to take note in its review of the documents and include these changes as they affect work or details in other areas not specifically referenced here.

**PAGE(S)**

**CHANGE**

BF-1-R1      Replace BF- 1 of the Contract documents with page BF-1-R1, which is included in this addendum.

Contract Pay Item No. 206, "Remove HMA Pavement", changed Estimated Quantity from "3500" to "470".

2. Questions and Answers

**Q:** What is the Engineer's estimate for this project?

**A:** \$70,555

**Q:** If concrete curb and gutter removal / replacement is required to install the sanitary sewer (main line), would it be included in Pay Item # 305?

**A:** No, Items 208 & 210 would cover concrete curb and gutter removal and replacement, respectively.

**Q:** Are we to perform the standard City of Ann Arbor sanitary sewer testing?

**A:** Yes.

**Q:** Do we need to wait 30 days to perform the TV and mandrel testing?

**A:** The sanitary sewer will need to be tested in accordance with the City's Standard Specifications, including an air test, a 30-day mandrel test and a televised inspection.

**Q:** Based on the project schedule, can it be assumed that the sanitary sewer trench must be paved AFTER all sanitary testing has been completed?

**A:** The final HMA patch for the sanitary sewer will not be approved until the sewer has passed the required testing in accordance with the City of Ann Arbor Public Services Department Standard Specification.

**Q:** Are we required to connect to the existing sanitary sewer lead to 2250 Belmont during this project?

**A:** No. The Contractor is only required to construct the new lead to the right-of-way.

**Q:** Are we to perform the standard City of Ann Arbor sanitary sewer testing?

**A:** Yes.

**Q:** Do we need to wait 30 days to perform the TV and mandrel testing?

**A:** The sanitary sewer will need to be tested in accordance with the City's Standard Specifications, including an air test, a 30-day mandrel test and a televised inspection.

**Q:** Based on the project schedule, can it be assumed that the sanitary sewer trench must be paved AFTER all sanitary testing has been completed?

**A:** The final HMA patch for the sanitary sewer will not be approved until the sewer has passed the required testing in accordance with the City of Ann Arbor Public Services Department Standard Specification.

**Q:** Are we required to connect to the existing sanitary sewer lead to 2250 Belmont during this project?

**A:** No. The Contractor is only required to construct the new lead to the right-of-way.

BID FORM

Section 1–Schedule of Prices

Project: Belmont Sanitary Sewer Extension Project  
 File #: 2013-029 Bid #: 4299

<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
111	Type II Lighted Barricade (Drum), Furnished	Each	15	\$ _____	\$ _____
112	Type II Lighted Barricade (Drum), Of Operated	Each	15	\$ _____	\$ _____
113	Type III Lighted Barricade, Furnished & Operated	Each	2	\$ _____	\$ _____
115	Temporary Type B Signs	SF	110	\$ _____	\$ _____
130	Protective Fencing	LF	20	\$ _____	\$ _____
200	General Conditions, Special, Maximum - \$8,000	LS	1	\$ _____	\$ _____
202	Minor Traffic Control, Special, Maximum - \$2,000	LS	1	\$ _____	\$ _____
203	Audiovisual Tape Coverage, Special	LS	1	\$ _____	\$ _____
204	Clean-Up & Restoration, Special	LS	1	\$ _____	\$ _____
205	No Parking Signs	Each	65	\$ _____	\$ _____
206	Remove HMA Pavement	SY	470	\$ _____	\$ _____
207	Subgrade Undercutting, Type II	CY	50	\$ _____	\$ _____
208	Remove Conc. Curb & Gutter, Any Type	LF	10	\$ _____	\$ _____
209	Remove Conc. S/Walk & Drive, Any Thickness	SF	200	\$ _____	\$ _____
210	Concrete Curb & Gutter, Any type	LF	10	\$ _____	\$ _____
211	6" Sidewalk, Ramp or Drive Approach	SF	200	\$ _____	\$ _____

TOTAL THIS PAGE \$ \_\_\_\_\_  
 (Also to be entered on page BF-2)