

**ADDENDUM NO. 1
TO
BID DOCUMENTS FOR THE
LIBERTY STREET, HARVARD PLACE, ARLINGTON BOULEVARD
SANITARY SEWER EXTENSIONS PROJECT
FOR THE
CITY OF ANN ARBOR, MICHIGAN**

The following changes, additions, and/or deletions shall be made to the Bid Documents for the Liberty Street, Harvard Place, and Arlington Boulevard Sanitary Sewer Extensions Project, for the City of Ann Arbor, Michigan, Bid No. ITB-4345.

The information contained herein shall take precedence over the original documents and all previous addenda, and is appended thereto. **This Addendum includes 8 page(s).**

The Contractor is to acknowledge receipt of this Addendum No. 1 on page P-1 of the Bid Documents prior to submitting its Proposal.

Changes in the Bid Documents which are outlined below are referenced to a page or drawing in which they appear conspicuously. The Bidder is to take note in its review of the documents and include these changes as they affect work or details in other areas not specifically referenced here.

Item #1: Contract Plan Set; replace all plan sheets with those included in the following files.

- Addendum 1 _Liberty-Harvard-Arlington 34x22_Revised Bid Plan Sheets.pdf

Changes include the following:

Plan Sheet 2 – Revised notations to reflect project pay items, and revised “Trench Detail – Type I Modified to show minimum width dimensions.

Plan Sheet 3 – Revised “Construction Notes” to remove all references to water main work, added “Miscellaneous Quantity” table, removed MDEQ Water Main Construction Permit as a requirement for this project, and updated AT&T contact information in “Contact Information” table.

Plan Sheets 4, 6, and 9 – Revised and/or added notations regarding channelizing devices/plastic drums, and revised the “Removal Key” to reflect project pay items.

Plan Sheets 5, 8, and 11 – Revised all PVC pipe notations from to SDR 35 to SDR 26, revised all sanitary sewer lead pipe size notations from four inch (4”) to six inch (6”) diameter to reflect project pay items, and revised the “Construction Key” to reflect project pay items.