

# CITY OF ANN ARBOR ENGINEERING

FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WITH PUBLIC ACT 174 OF 2013, THE CONTRACTOR SHALL CALL 811 OR


ELECTRICAL POWER, CABLE TV AND FIBER OPTIC LINES ARE FOR THEIR ACCURATE REPRESENTATION IN THIS DRAWING. MISS DIG MUST

STANDARD SPECIFICATIONS, IT'S DETAILS, WHICH ARE INCLUDED BY REFERENCE, AND THIS PROJECT'S CONTRACT DOCUMENTS. THE OMISSION OF ANY CURRENT STANDARD DETAIL DOES NOT RELIEVE THE CONTRACTOR

# 2019 MISC UTILITY PROJECTS

ITB 4556, FILE No. 2018025

	SHEET LIST TABLE					
SHEET NUMBER	SHEET TITLE					
1	COVER SHEET					
2	STANDARD NOTES					
3	LEGEND					
4	WATER MAIN DETAILS					
5	STORM SEWER, TRENCH AND MISC. DETAILS					
6 - 8	TYPICAL SECTIONS					
9	TPAR WALKWAY DEVICES					
10	ALTERNATE PEDESTRIAN ROUTE (APR) DETOUR					
11	TPAR RAMPS					
12	ALTERNATE PEDESTRIAN ROUTE (APR) BYPASS					
	BUCHOLZ COURT					
13	MAINTENANCE OF TRAFFIC					
14	REMOVALS					
15	WATER MAIN PLAN AND PROFILE					
16	ROAD					
	CEDAR BEND DRIVE					
17	REMOVALS AND MAINTENANCE OF TRAFFIC					
18	WATER MAIN PLAN AND PROFILE					
19	ROAD					
	MAYWOOD AVENUE					
20	MAINTENANCE OF TRAFFIC					
21 - 22	REMOVALS					
23 - 26	WATER MAIN PLAN AND PROFILE					
27 - 29	STORM SEWER PLAN AND PROFILE					
30 - 31	ROAD					



TESHA HUMPHRISS, P.E. - MI LICENSE No. 51103 **PROJECT MANAGER** 

3 / 1 /2019



#### **CONSTRUCTION NOTES:**

- 1. Driveways and entrances to buildings, real property, and the like shall not be blocked except for short durations and only when approved by the Engineer. Vehicular and pedestrian access shall be maintained at all times. It shall be the Contractor's responsibility to coordinate all necessary driveway closures with the property owner(s) and resident(s) in the areas of construction.
- 2. The location and depth of all existing utilities and service leads are to be field verified by the Contractor prior to construction.
- 3. Location and depth of utilities as depicted on the plans is approximate and shown according to the best information available. It is the Contractor's responsibility to excavate ahead and adjust depth of conflict utilities accordingly. Any damage to utilities is the Contractor's responsibility to avoid and/or repair as necessary.
- 4. The Contractor is to take special care to protect the existing water main and be responsible for maintaining consistent water service.
- 5. During non—working hours no trench shall remain open; any open trench shall be properly secured with protective fencing. This work shall be included in the item of work "General Conditions".
- 6. Trenches for new water services shall be excavated to MIOSHA and City of Ann Arbor Public Works requirements.
- 7. City of Ann Arbor Public Works will install the corporation and copper service lead(s) to transfer the connection(s). If an existing water service is found to be failing or is not copper, the lead will be replaced to the curb box by Public Works.
- 8. For the installation of corporations, or any other related activities, the Contractor shall not receive additional compensation for delays due to the scheduling of or coordination with the City of Ann Arbor Public Works.
- 9. The Contractor shall backfill trenches in accordance with Trench Detail specified on plans. This work shall be included in the item of work "Excavate and Backfill for Water Service Tap and Lead". All concrete removals and replacements required for this work will be paid for separately.
- 10. All ductile iron pipe and fittings shall be polyethylene wrapped per ANSI/AWWA C105/A21.5.
- 11. Cor—blu bolts to be used at all mechanical water main joints at hydrants and Megalug fittings
- 12. The Contractor shall construct, flush, and bacteriologically test the water main per Detailed Specification "Water Main Installation and Testing" and as approved by the Engineer. All chlorinated water shall be discharged directly into an approved sanitary sewer. The Contractor shall supply all necessary hoses, fittings and the like to accomplish this work.
- 13. Water main fittings, other than those specifically listed as separate pay items, which are required to complete the work, such as blow—off assemblies, concrete thrust blocks, solid sleeves and mechanical plugs, shall not be paid for separately, but shall be included in the pipe pay items.
- 14. "No Parking" signs shall be installed by the Contractor at locations as approved or directed by the Engineer. All signs shall be installed in accordance with the detailed specifications.

- 15. Postal delivery and refuse pickup service shall be maintained at all times by the Contractor.
- 16. All fittings, hydrants, valves and castings removed during construction are the property of the City of Ann Arbor. The Contractor within 48 hours shall deliver to City of Ann Arbor Public Works Facility at the W.R. Wheeler Service Center located at 4251 Stone School Road.
- 17. Where street curbs are undermined due to construction activities, they shall be removed and replaced as directed by the Engineer.
- 18. The Contractor shall be responsible for the continuous maintenance of the temporary road surface and soil erosion control measures within the construction area until the full completion of the project. This work shall be included in the item of work "General Conditions".
- 19. All curb, sidewalk, driveway approach removals shall be approved by Engineer before the work is done.
- 20. Sawed sewer pipe connections shall be coupled with a Fernco flexible coupling and a stainless steel shear ring.
- 21. The location of material stock piles and on—site staging areas to be approved by the Engineer.
- 22. All structures shall receive new castings as directed by the Engineer, as specified on the standard casting schedule. The existing castings are the property of the City of Ann Arbor. The Contractor shall deliver to City of Ann Arbor Public Works Facility at the W.R. Wheeler Service Center located at 4251 Stone School Road.
- 23. Payment for drainage structure sumps, where specified, shall be included in the payment for the various drainage structure sizes and or types.
- 24. Where sewer pipes of different sizes or materials are joined, Fernco flexible couplings with stainless steel shear rings shall be used. The Contractor's purchase price for these devices, including shipping, shall be paid as an extra. Prior to payment for this item, the Contractor shall submit receipts for the Engineer's review and approval. All other costs associated with the installation of these devices shall be included in the payment for the sewer.
- 25. Where sewer and water main are to be removed & replaced or added, all pipe shall be installed using Trench Detail detailed in the specifications or shown on Plans. Backfill for sewer and water construction shall be MDOT Granular Material, Class II. Modified.
- 26. Existing street name, guide, and regulatory signs, and mailboxes which conflict with the proposed construction shall be removed prior to construction, stored in a manner which will prevent damage, and re—set in locations as directed by the Engineer. This work will not be paid for separately, but shall be included in "Machine Grading, Modified"
- 27. In areas where edge drain cannot be installed in accordance with City of Ann Arbor Detail SD—TD—11, the edge drain shall be installed at the depth as indicated on the plans, or as directed by Engineer. In no case shall the edge drain be installed at a grade less than 0.50% or at a depth of less than 2' below top of proposed pavement.

#### GENERAL

NOTIFY THE CITY OF ANN ARBOR SOIL EROSION CONTROL OFFICE 48 HOURS PRIOR TO BEGINNING WORK ON THE PROJECT. PHONE: 734-794-6265.

- 1. THE CONTRACTOR SHALL IMPLEMENT AND MAINTAIN THE SOIL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER AT ALL TIMES DURING CONSTRUCTION. ANY MODIFICATIONS OR ADDITIONS TO THE SOIL EROSION CONTROL MEASURES DUE TO CONSTRUCTION OR CHANGED CONDITIONS SHALL BE AS DIRECTED AND APPROVED BY THE ENGINEER.
- 2. ALL SOIL EROSION AND SEDIMENTATION CONTROL WORK SHALL CONFORM TO THE PERMIT REQUIREMENTS OF THE CITY OF ANN ARBOR, CITY ORDINANCE CHAPTER 63, CITY OF ANN ARBOR STANDARDS DIVISION VII, THE LAWS OF THE STATE OF MICHIGAN, AND THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
- 3. DAILY, OR AFTER ANY STORM EVENT, INSPECTIONS OF EROSION CONTROL MEASURES SHALL BE MADE BY THE CONTRACTOR. PERIODIC INSPECTIONS MAY BE MADE BY THE ENGINEER TO DETERMINE THE EFFECTIVENESS OF EROSION AND SEDIMENTATION CONTROL MEASURES. ANY NECESSARY CORRECTIONS SHALL BE MADE WITHOUT DELAY, AND WITHOUT ADDITIONAL COST TO THE CITY OF ANN ARBOR.
- 4. EROSION AND SEDIMENTATION FROM WORK ON THE SITE SHALL BE CONTAINED ON THE SITE AND NOT BE ALLOWED TO COLLECT ON ANY OFF-SITE AREAS, ROADWAYS OR WATERWAYS.
- 5. ALL MUD/SOIL TRACKED ONTO ROADWAYS FROM THE SITE DUE TO CONSTRUCTION, SHALL BE PROMPTLY REMOVED BY THE CONTRACTOR. IF SO ORDERED, THE CONTRACTOR SHALL PROVIDE AND OPERATE A VACUUM-TYPE STREET SWEEPER, AT NO ADDITIONAL COST TO THE CITY OF ANN ARBOR, WITHIN FOUR (4) HOURS OF BEING SO ORDERED.
- 6. RESTORATION OF ALL DISTURBED AREAS, INCLUDING PLACEMENT OF TOPSOIL, SEED, FERTILIZER AND MULCH AND/OR SOD SHALL BE PERFORMED WITHIN FIVE (5) DAYS OF THE COMPLETION OF FINAL CRADE
- 7. CONSTRUCTION OPERATIONS SHALL BE SCHEDULED AND PERFORMED SO THAT PREVENTATIVE SOIL EROSION CONTROL MEASURES ARE IN PLACE PRIOR TO EXCAVATION IN CRITICAL AREAS AND TEMPORARY STABILIZATION MEASURES ARE IN PLACE IMMEDIATELY FOLLOWING BACKFILLING OPERATIONS.
- 8. SPECIAL PRECAUTIONS WILL BE TAKEN IN THE USE OF CONSTRUCTION EQUIPMENT TO PREVENT SITUATIONS THAT PROMOTE EROSION.
- 9. PROPER DUST CONTROL SHALL BE MAINTAINED DURING CONSTRUCTION BY USE OF WATER TRUCKS AND/OR DUST PALLATIVE AS REQUIRED.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY SOIL EROSION CONTROL MEASURES AND REMOVAL OF SOME MEASURES UPON AUTHORIZED COMPLETION OF THE PROJECT. FINAL COMPLETION OF PROJECT WILL NOT BE AUTHORIZED UNTIL ALL SITE WORK AND UTILITY CONSTRUCTION IS COMPLETE AND ALL SOILS ARE STABILIZED.
- 11. THE CONTRACTOR SHALL NOT GRADE INTO ADJACENT PROPERTIES. SILT AND PROTECTIVE FENCE SHALL BE INSTALLED AND MAINTAINED TO PREVENT GRADING, EROSION AND SEDIMENTATION INTO THE ADJACENT PROPERTIES.
- 12. TREE PROTECTION FENCING MUST REMAIN INTACT UNTIL RESTORATION OF THE SITE IS COMPLETE.

#### SEQUENCE OF EROSION CONTROL MEASURES:

- THE CONTRACTOR IS TO SUBMIT TO THE ENGINEER, A SEQUENCE OF CONSTRUCTION WITH RESPECT TO THE SOIL EROSION CONTROL MEASURES FOR REVIEW, COMMENT AND APPROVAL. THIS SCHEDULE IS TO INCLUDE INSPECTION AND REPAIR OF ALL TEMPORARY EROSION CONTROL MEASURES DAILY AND WITHIN 24 HOURS OF A STORM EVENT.
- SAMPLE SOIL EROSION AND SEDIMENTATION CONTROL INSTALLATION MINIMUM REQUIREMENTS:

  1.1. INSTALL SILT FENCE, TREE PROTECTION FENCING, MUD MATS, INLET FILTERS ON EXISTING DRAINAGE
  FEATURES, AND ALL OTHER TEMPORARY SOIL EROSION CONTROLS, PRIOR TO ANY CLEARING OR
  EARTH MOVING OPERATION.
- 1.2. STRIP AND STOCKPILE TOPSOIL. STABILIZE STOCKPILE AS REQUIRED.
- 1.3. INSTALL WATER MAINS, STORM AND SANITARY SEWERS, AND OTHER ENCLOSED DRAINAGE FEATURES. NEW INLET FILTERS SHALL BE INSTALLED IMMEDIATELY FOLLOWING INSTALLATION OF NEW DRAINAGE INLETS.
- 1.4. PERFORM MACHINE GRADING OPERATIONS AND CONSTRUCT PAVEMENTS (MAINLINE, SIDEWALKS, DRIVES, ETC.).
- 1.5. CONTINUALLY MAINTAIN EROSION AND SEDIMENTATION CONTROL MEASURES, AS REQUIRED TO ALLOW DRAINAGE AND SEDIMENT REMOVAL. REMOVE ANY ACCUMULATED SEDIMENT IMMEDIATELY.
- 1.6. COMPLETE ALL FINE GRADING.
- 1.7. TEMPORARY SEED AND INSTALL EROSION CONTROL BLANKET IN ALL DISTURBED AREAS.
- 1.8. REFER TO LANDSCAPE PLANTING PLANS FOR PERMANENT SITE STABILIZATION.
- 1.9. CLEAN OUT STORM SEWER SYSTEMS.
- 1.10. REMEDY ANY NOTED DEFECTS TO THE SATISFACTION OF THE CITY OF ANN ARBOR'S SOIL EROSION AND SEDIMENTATION CONTROL OFFICIAL.
- 1.11. ALL TEMP. SOIL EROSION CONTROL MEASURES MUST BE REMOVED, WITH ENGINEERS APPROVAL, PRIOR TO FINAL INSPECTION
- NOTE: THIS SEQUENCE IS FOR INFORMATION ONLY. IT IS INTENDED TO SHOW THE SEQUENCE OF CONSTRUCTION WITH RESPECT TO THE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES. THE CONTRACTOR IS RESPONSIBLE FOR SUBMITTING THEIR OWN DETAILED CONSTRUCTION SEQUENCE AND SCHEDULE TO THE ENGINEER FOR REVIEW, COMMENT, AND APPROVAL.

#### TEMPORARY SEEDING:

- 1. SEED IN ACCORDANCE WITH PROJECT DRAWINGS AND SPECIFICATIONS.
- 2. ANY DISTURBED AREA NOT PAVED, SEEDED, MULCHED, SODDED OR BUILT UPON BY NOVEMBER 15TH OR JUNE 30TH IS TO BE TEMPORARILY STABILIZED PER SPECIFICATIONS.

## PERMITS REQUIRED TO BE OBTAINED BY THE CONTRACTOR PRIOR TO THE BEGINNING OF CONSTRUCTION.

PERMIT	ISSUING AUTHORITY
LANE CLOSURE PERMIT*	CITY OF ANN ARBOR ENGINEERING
"NO PARKING" SIGNS PERMIT*	CITY OF ANN ARBOR ENGINEERING
GRADING/SOIL EROSION & SEDIMENTATION CONTROL PERMIT*	CITY OF ANN ARBOR CUSTOMER SERVICE
RIGHT-OF-WAY PERMIT*	CITY OF ANN ARBOR CUSTOMER SERVICE
* NO COST TO	CONTRACTOR

## PERMITS REQUIRED TO BE OBTAINED BY THE CITY OF ANN ARBOR PRIOR TO THE BEGINNING OF CONSTRUCTION.

PERMIT	ISSUING AUTHORITY
M.D.E.Q. WATER MAIN CONSTRUCTION PERMIT	MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY
M.D.E.Q. SANITARY SEWER CONSTRUCTION PERMIT	MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY

<b>PUBLIC UTILITIES</b>	OWNER	CONTACT
WATER		
SANITARY		
STORM	CITY OF ANN ARBOR PUBLIC WORKS W.R. WHEELER SERVICE CENTER 4251 STONE SCHOOL ROAD	(734) 794–6350
FORESTRY	ANN ARBOR, MI 48108	
SIGNS SIGNALS STREET LIGHTS		CHUCK FOJTIK (734) 794-6361
PRIVATE UTILITIES	OWNER	CONTACT
GAS	DTE ENERGY 3150 E. MICHIGAN AVE, YPSILANTI TOWNSHIP, MI 48198	ROBERT CZAPIEWSK (734) 544–7818
ELECTRIC	DTE ENERGY WESTERN WAYNE SERVICE CENTER 8001 HAGGERTY ROAD BELLEVILLE, MI 48111	ANTHONY IGNASIAK (734) 397-4447
CABLE	COMCAST 27800 FRANKLIN ROAD SOUTHFIELD, MI 48034	RON SUTHERLAND (313) 999-8300
PHONE	AT&T 550 S. MAPLE ROAD ANN ARBOR, MI 48103	JEFF LEHMAN SR (734) 996-5334
FIBER OPTIC	MCI 2800 N. GLENFILLE ROAD RICHARDSON, TX 75082	DEAN BOYERS (972) 729-6016
FIBER OPTICS	WINDSTREAM 1295 S LINDEN ROAD, SUITE B FLINT, MI 48532	GREG SERICH (810) 244-3500
STREET LIGHTING	DTE ENERGY 8001 HAGGERTY ROAD BELLEVILLE, MI 48111	LANCE ALLEY (734) 397-4188

		BUCHOLZ COURT BENCHMARKS
BM#	ELEV	DESCRIPTION
1	857.876	LAG SCREW IN W. FACE OF PP @ SE CORNER OF ARBANA DRIVE AND MARK HANNAH, BK 1112A PG 27
2	852.679	STEAMER VALVE ON FIRE HYDRANT, BK 1112A PG 28
3	849.550	SET RR SPIKE IN N. SIDE OF U.P. ON S. SIDE OF BATH STREET IN FRONT OF HSE NO. 1011
4	845.396	SET RR SPIKE IN E. SIDE OF U.P. ON W. SIDE OF BUCHOLZ CT. BETWEEN HSE NO. 301 AND 303.

PROJ

UTILITY


2019

S

ARBO

		MAYWOOD AVENUE BENCHMARKS
BM#	ELEV	DESCRIPTION
1	967.339	TOP, S. SIDE OF CONC. BASE FOR L.P. @ N.E. CORNER OF STADIUM AND ARELLA/MAYWOOD.
2	966.448	SET RR SPIKE IN E. SIDE OF U.P. ON W. SIDE OF MAYWOOD BETWEEN HSE NO. 1402 AND 1611 STADIUM BLVD.
3	962.504	TOP OF SE ANCHOR BOLT FOR L.P. ON W. SIDE OF MAYWOOD BETWEEN HSE NO. 1476 AND 1406.
4	960.651	TOP OF SE ANCHOR BOLT FOR L.P. ON W. SIDE OF MAYWOOD IN FRONT OF HSE NO. 1496.
5	956.842	TOP OF SE ANCHOR BOLT FOR L.P. ON W. SIDE OF MAYWOOD IN FRONT OF HSE NO. 1500.
6	948.232	SET RR SPIKE IN S. SIDE OF L.P. @ N.E. CORNER OF AVONDALE AND MAYWOOD.

		CEDAR BEND DRIVE BENCHMARKS
BM#	ELEV	DESCRIPTION
1	780.536	RR SPIKE IN E. SIDE OF U.P. ON E. SIDE OF CEDAR BEND DRIVE, 2ND POLE N. OF FULLER RD. BK 1116 PG 40.
2	776.316	TOP, S. SIDE OF CONC. BASE FOR SIGNAL POLE AT NE CORNER OF CEDAR BEND DRIVE AND FULLER ROAD.



**GATE WELL FOR MAIN 16" & SMALLER** 

MINIMUM STANDARDS

THE MDOT GRADE PI OR P-NC CONCRETE AT THE FITTING FACE SHALL EXTEND TO WITHIN 2 INCHES OF THE BELL AND SHALL EXTEND FROM THE FITTING FACE A MINIMUM OF 2 FEET TO THE UNDISTURBED SOLID GROUND.


THE DIMENSIONS OF THE THRUST BLOCK AT THE FACE OF THE UNDISTURBED SOLID GROUND SHALL BE AS SHOWN IN THE TABLE BELOW.

IF THERE ISN'T SUFFICIENT SPACE FOR THE INSTALLATION OF THE THRUST BLOCK WITHOUT INTERFERENCE WITH OTHER SERVICES, ANOTHER ARRANGEMENT SATISFACTORY TO THE ENGINEER SHALL BE USED.

FITTINGS		110				DEN	NDS					
FITTINGS		UG				DEI	2עוי				l	
I.D.	TE	ΞE	9	<b>α</b> •	1 4	5°	22	· 1°	11	<u>1</u> •	HYDF	RANT
	CRO	DSS	3	U	T	_	~	-2	11	4		
INCHES	W	Н	W	Η	W	Η	W	Η	W	H	W	Ι
4	1.0	1.0	1.0	1.0	1.0	1.0						
6	2.0	1.5	2.0	2.0	2.0	1.0	1.0	1.0	1.0	1.0	2.0	1.5
8	2.5	2.0	3.5	2.0	2.0	2.0	2.0	1.0	1.0	1.0	2.5	2.0
12	3.5	3.0	5.5	3.0	3.5	2.5	2.0	2.0	2.0	1.0		
16	6.0	35	60	40	50	30	35	25	20	20		


16 | 6.0 | 3.5 | 6.0 | 4.0 | 5.0 | 3.5 | 2.5 | 2.0 | 2.0 | FOR FITTING SIZES LARGER THAN 16", THRUST BLOCK DIMENSIONS SHALL BE AS SPECIFIED BY ENGINEER.

W = WIDTH IN FEET H = HEIGHT IN FEET



THESE ARE MINIMUM STANDARDS. WHERE SOIL CONDITIONS DICTATE, ADJUSTMENTS IN SIZE SHALL BE MADE AS DIRECTED BY THE PUBLIC SERVICES AREA ADMINISTRATOR.


THRUST BLOCK



NOTE: FOLLOW ANSI/AWWA C105/A21.5-05 REVISION OF ANSI/AWWA C105/A21.5-99 FOR CONSTRUCTION AND INSTALLATION METHODS. USE MODIFIED METHOD A


APPLIES TO: POLYETHYLENE WRAPPED D.I. WATERMAIN SEE PLANS FOR LOCATIONS


#### POLYETHYLENE ENCASEMENT (DRY INSTALLATION)




APPLIES TO: POLYETHYLENE WRAPPED D.I. WATERMAIN SEE PLANS FOR LOCATIONS

### POLYETHYLENE ENCASEMENT (WET INSTALLATION)







FINAL SURFACE COURSE

**WATER VALVE BOX ADJUSTMENT** 

**PROJE**( ENGINEERING UTILITY MISC


ERVICES

**OF ANN ARBOR** 

CITY

4 OF 31

2019





STANDARD MANHOLE (TYPE I)

ASPHALT PAVEMENT 24" STD.

TREE PROTECTION DETAIL

**CURB AND GUTTER, CONC, DET F4, SPECIAL** 






TRENCH DETAIL - TYPE I

SD-TD-1, MODIFIED

4. 2' SUMP REQUIRED ON ALL DRAINAGE


STRUCTURES.



**UTILITY TRENCH-TYPE II,** 

SD-TD-2, (MODIFIED)

(UNDER GRAVEL ROAD)



TRENCH DETAIL FOR UNDER DRAIN (UNDER HMA PAVEMENT)


BY THE ENGINEER BASED ON EXISTING SITE CONDITIONS,

INCLUDING CONDITION OF THE SUBGRADE.

**PROJECT** - ENGINEERING UTILITY MISC SERVICES 2019


ARBOR ANN CITY


SHEET No.



		HMA APPLICA	ATION ESTIN	MATE	
нма міх	RATE OF APPLICATION	THICKNESS (INCHES)	AWI (MIN.)	BINDER	LOCATION/NOTES
LVSP	220 LB/SYD	2.0	260 (TOP)	PG 58-28	TOP COURSE
LVSP	220 LB/SYD	2.0	_	PG 58-28	LEVELING COURSE
Bond Coat SS—1h	0.10 GAL/SYD	-	_	-	INCLUDE IN COST OF HMA ITEM

DE ANN ABBOR - P	IIBI IC SEBVICES - ENGINEERING	ANA						
		CITY OF ANN ARBOR						
ç.								
	2019 MISC UTILITY PROJECTS	TO BEAT HURON STREET						
	TYPICAL SECTIONS	D.O. BOX 8647  P.O. BOX 8647  ANN ARBOR, MI 48107-8647						
.0.7		734-794-6410 www.a2gov.org	00 OUT FOR BID		3-1-19	CC/DF/KB	TH Kno	Know what's below.
9-	HOCHOLZ COURT	WCH IGN	REV.	DESCRIPTION	DATE	DRAWN CHECKED		all before you dig.





		HMA APPLICA	ATION ESTI	MATE	
нма міх	RATE OF APPLICATION	THICKNESS (INCHES)	AWI (MIN.)	BINDER	LOCATION/NOTES
LVSP	220 LB/SYD	2.0	260 (TOP)	PG 58-28	TOP COURSE
LVSP	220 LB/SYD	2.0	_	PG 58-28	LEVELING COURSE
Bond Coat SS-1h	0.10 GAL/SYD	-	_	-	INCLUDE IN COST OF HMA ITEM


CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING


PARAMER NTS


TYPICAL SECTIONS


TYPICAL SECTIONS

25 Misc Utility 2019\Plan Production\2018025Det.dwg Dwg Created: 27—Feb-









NARROW TEMPORARY PEDESTRIAN ACCESS ROUTE PASSING DETAIL

RAILINGS OR OTHER OBJECTS MAY PROTRUDE A MAXIMUM OF 4 INCHES INTO THE WALKWAY CLEAR

ANY PEDESTRIAN DEVICES USED TO PROVIDE POSITIVE PROTECTION FOR PEDESTRIANS OR WORKERS SHALL MEET NCHRP 350 CRASHWORTHY REQUIREMENTS APPROPRIATE FOR THE BARRIER'S

BARRICADES SHALL BE PLACED CONTINUOUSLY ACROSS THE ENTIRE WIDTH OF THE WALKWAY

- (1) ANY TRIPPING HAZARD IN THE WALKWAY NEEDS A DETECTABLE EDGE. BALLAST SHALL BE LOCATED BEHIND OR INTERNAL TO THE DEVICE. ANY SUPPORT ON THE FRONT OF THE DEVICE SHALL NOT EXTEND INTO THE 48 INCH MINIMUM WALKWAY CLEAR SPACE AND SHALL NOT EXCEED 0.5 INCHES IN
- (2) DETECTABLE EDGES SHALL BE CONTINUOUS AND A MINIMUM OF 6 INCHES IN HEIGHT ABOVE
- (3) DEVICES SHALL NOT BLOCK WATER DRAINAGE FROM THE WALKWAY. A GAP HEIGHT OR OPENING FROM THE WALKWAY SURFACE UP TO A MAXIMUM OF 2 INCHES IS ALLOWED FOR DRAINAGE
- BE IN A VERTICAL PLANE PERPENDICULAR TO THE WALKWAY ABOVE THE DETECTABLE EDGE. - BE CONTINUOUS AT A HEIGHT OF 34 TO 38 INCHES ABOVE THE WALKWAY SURFACE, AND
- 5 ALL DEVICES SHALL BE FREE OF SHARP OR ROUGH EDGES, AND FASTENERS (BOLTS) SHALL BE
- 6 ALL DEVICES USED TO CHANNELIZE PEDESTRIAN FLOW SHOULD INTERLOCK SUCH THAT GAPS DO NOT ALLOW PEDESTRIANS TO STRAY FROM THE INTENDED CHANNELIZED PATH.
- (7) A WALKWAY SURFACE SHALL BE FIRM, STABLE, AND SLIP RESISTANT. COMPACTED GRAVEL,

2019 MISC UTILITY PROJECTS CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

#### PEDESTRIAN DETOUR USING OPPOSITE SIDE OF STREET

## W11-2 30"x30" W16-7PL 24"x12" CROSS HERE R9-11AR 24"x12" 5 ENDS OCT 20XX CONTACT 734-XXX-XXXX W11-2 30"x30" SIDEWALK CLOSED AHEAD SIDEWALK CLOSED SIDEWALK CLOSED CROSS HERE CROSS HERE R9-11 24"x12" ENDS OCT 20XX CONTACT 734-XXX-XXXX ENDS OCT 20XX CONTACT 734-XXX-XXXX SIDEWALK CLOSED R9-9 24"x12" CROSS HERE

OTHER SIDE OF STREET DETOUR OR DETOUR WITH TRAILBLAZING SIGNS

(FOR CORNER SIDEWALK CLOSURE WITH OPTIONAL TEMPORARY CROSSWALK)

#### GENERAL NOTES

WHEN CLOSING OR RELOCATING CROSSWALKS OR SIDEWALKS, THE CONTRACTOR SHALL PROVIDE DETECTABLE TEMPORARY FACILITIES AND INCLUDE ACCESSIBILITY FEATURES CONSISTENT WITH EXISTING PEDESTRIAN FACILITIES.

TEMPORARY TRAFFIC CONTROL DEVICES FOR PEDESTRIANS ARE SHOWN. OTHER DEVICES MAY BE NECESSARY TO CONTROL VEHICULAR TRAFFIC. STAGE WORK, AS NECESSARY, TO PROVIDE AN ALTERNATE PEDESTRIAN ROUTE (APR) AT ALL TIMES. FOR ROADWAYS WITH NO AVAILABLE DETOURS, MAINTAIN ONE OPEN SIDEWALK AT ALL TIMES.

PROVIDE A SMOOTH, CONTINUOUS, HARD SURFACE THROUGH THE LENGTH OF THE APR. COMPACTED GRAVEL, AGGREGATE, OR SLAG MATERIALS ARE NOT ALLOWED. PROVIDE A FIRM, STABLE, AND SLIP RESISTANT TEMPORARY WALKWAY SURFACE TO COVER SHORT SEGMENTS OF ROUGH, SOFT, OR UNEVEN GROUND.

THE PEDESTRIAN TRAFFIC SIGNALS CONTROLLING CLOSED CROSSWALKS SHALL BE COVERED OR DEACTIVATED BY THE CITY OF ANN ARBOR. THE CONTRACTOR SHALL SCHEDULE AND COORDINATE THIS WORK WITH THE ENGINEER A MINIMUM OF 72 HOURS (NOT INCLUDING WEEKENDS & HOLIDAYS) PRIOR TO THE BEGINNING OF WORK THAT REQUIRES A SIDEWALK CLOSURE.

POST MOUNTED SIGNS LOCATED ADJACENT TO A SIDEWALK SHALL HAVE A 7 FOOT MINIMUM CLEARANCE FROM THE BOTTOM OF THE SIGN TO THE SIDEWALK SURFACE.

WHEN THE ENGINEER DETERMINES THAT THE CONTRACTOR'S OPERATIONS OR PLACEMENT OF TRAFFIC CONTROL DEVICES HAS CAUSED A SITUATION THAT THE VISIBILITY OF IS REDUCED ENOUGH TO CREATE A HAZARD, THE TRAFFIC CONTROL DEVICES SHALL BE DELINEATED WITH FLAGS OR OTHER ENGINEER-APPROVED DEVICES AT NO ADDITIONAL COST TO THE PROJECT.

MINIMIZE DISRUPTION TO PEDESTRIANS TO THE MAXIMUM EXTENT FEASIBLE BY PROVIDING AN APR IN THE FOLLOWING ORDER OF PREFERENCE:


- 1. PROVIDE THE APR ON THE SAME SIDE OF THE STREET AS THE DISRUPTED ROUTE UTILIZING BYPASSES.
- 2. WHERE IT IS NOT FEASIBLE TO PROVIDE A SAME SIDE APR, PROVIDE A DETOUR ON THE OTHER SIDE OF THE STREET.
- 3. WHERE IT IS NOT FEASIBLE TO PROVIDE AN APR ON THE OTHER SIDE OF THE ROADWAY, PROVIDE AN APR DETOUR WITH TRAILBLAZING SIGNS AS SHOWN ON THE PROJECT PLANS.

#### SPECIFIC NOTES

- 1) TEMPORARY CURB RAMPS WITH DETECTABLE WARNINGS.
- (2) TEMPORARY PAVEMENT MARKING FOR CROSSWALK LINES.
- 3 AN APPROVED AUDIBLE MESSAGE DEVICE OR TACTILE MESSAGE SHALL BE PROVIDED FOR SIGHT-IMPAIRED PEDESTRIANS.
- 4 THE INTERNATIONAL SYMBOL OF ACCESSIBILITY SHOULD BE DISPLAYED WHEN ANY WALKWAY THROUGH A WORK ZONE HAS BEEN DETERMINED TO BE TPAR COMPLIANT. THE SYMBOL OF ACCESSIBILITY SHALL NOT BE DISPLAYED IF PERSONS WITH DISABILITIES SHOULD NOT USE THE PRIMARY TEMPORARY PEDESTRIAN DETOUR. THE REASON FOR THE NON-COMPLIANCE SHALL BE POSTED AND AN ALTERNATE ROUTE SHALL BE POSTED WHEN THE PRIMARY TEMPORARY PEDESTRIAN DETOUR IS NON-COMPLIANT TO TPAR STANDARDS.
- 5 TYPICAL SIGN MESSAGE FOR A TEMPORARY PEDESTRIAN DETOUR SHALL INCLUDE INFORMATION SUCH AS THE DURATION OF THE WALKWAY RESTRICTIONS (BEGINNING AND/OR END DATES) AND A PROJECT CONTACT NUMBER FOR 24 / 7 QUESTIONS OR REPORTING HAZARDS.
- 6 PEDESTRIAN DETOUR TRAILBLAZING SIGNS SHALL BE USED IF THE PEDESTRIAN DETOUR IS IN A LOCATION OTHER THAN ACROSS THE STREET FROM THE SIDEWALK CLOSURE.

#### PEDESTRIAN TEMPORARY TRAFFIC CONTROL NOTES

- 1. THE CONTRACTOR SHALL MAINTAIN PEDESTRIAN THROUGH MOVEMENTS FROM ONE END OF THE CONSTRUCTION AREA TO THE OTHER, ON AT LEAST ONE SIDE OF THE STREET DURING CONSTRUCTION. ANY SIDEWALK CLOSURES SHALL MEET THE REQUIREMENTS OF THE MMUTCD, PART 6.
- 2. PEDESTRIAN ACCESS SHALL BE PROVIDED TO ALL ADJACENT PROPERTIES, BUILDINGS, RESIDENCES AND COMMERCIAL PROPERTIES AT ALL TIMES. THIS MAY INCLUDE TEMPORARY WALKWAYS SPANNING THE CONSTRUCTION AREA.
- 3. IF SIDEWALKS ARE CLOSED, A TEMPORARY PEDESTRIAN ACCESS ROUTE (TPAR) SHALL BE PROVIDED ON THE SAME SIDE OF THE ROAD AS THE CLOSED SIDEWALK, IF POSSIBLE. SIGNS AND BARRICADES SHALL BE USED TO PROVIDE ADVANCE NOTICE OF THE CLOSURE AND THE ROUTE OF ANY PEDESTRIAN DETOURS. THE TPAR SHALL HAVE A MINIMUM UNOBSTRUCTED WIDTH OF 4 FEET. IF THE TPAR IS LESS THAN 5 FEET IN WIDTH, A 5 FOOT BY 5 FOOT PASSING SPACE SHALL BE PROVIDED AT LEAST EVERY 200 FEET. THE SURFACE OF THE TPAR SHALL BE SMOOTH AND CONTINUOUS FOR THE LENGTH OF THE TPAR. THE TPAR SHALL MAINTAIN THE SAME LEVEL OF ACCESSIBILITY AND DETECTABILITY AS THE FACILITY THAT IS BEING CLOSED. THE TPAR SHALL NOT LEAD PEDESTRIANS INTO CONFLICTS WITH VEHICLES, EQUIPMENT, OR CONSTRUCTION OPERATIONS.
- 4. IF THE TPAR IS ADJACENT TO MOVING TRAFFIC, CONSTRUCTION OPERATIONS/EQUIPMENT, OR DROP-OFFS, THEN CRASH WORTHY CHANNELIZING DEVICES THAT MEET THE REQUIREMENTS OF NCHRP 350 AND THE MMUTCD SHALL BE USED.
- 5. THE CONTRACTOR SHALL NOT STORE OR PLACE ANY CONSTRUCTION MATERIALS, EQUIPMENT OR SIGNS IN THE PEDESTRIAN PATH OF TRAVEL.
- 6. THE CONTRACTOR'S OPERATIONS SHALL NOT OCCUPY SIDEWALKS EXCEPT WHERE PROPER PROTECTION AND A TPAR HAVE BEEN PROVIDED.
- 7. WHEN DIRECTED BY THE ENGINEER, OR STATED ON THE PLANS, THE CONTRACTOR SHALL PROVIDE A TEMPORARY PEDESTRIAN TRAFFIC CONTROL PLAN FOR REVIEW AND WRITTEN APPROVAL BY THE ENGINEER A MINIMUM OF THREE WEEKS BEFORE SUCH PLAN IS IMPLEMENTED. THIS PLAN SHALL DETAIL THE CONSTRUCTION PHASING AND SCHEDULE AND THE SPECIFIC METHODS OF MAINTAINING SAFE PEDESTRIAN ACCESS THROUGHOUT THE CONSTRUCTION AREA. THIS PLAN SHALL PROVIDE THE LOCATION AND DETAILS OF TEMPORARY CONSTRUCTION SIGNING, MARKINGS, BARRICADES, CHANNELIZING DEVICES, TPARS AND METHODS TO MAINTAIN ACCESS TO ADJACENT PROPERTIES, BUSINESSES, RESIDENCES, ETC. NO WORK SHALL BE ALLOWED TO BEGIN UNTIL THIS PLAN IS APPROVED BY THE ENGINEER IN WRITING.
- 8. PROVISION OF THE TPAR AND ALL OF ITS ELEMENTS, INCLUDING BUT NOT LIMITED TO, CREATION OF THE TEMPORARY PEDESTRIAN CONTROL PLAN, SIGNS, CHANNELIZING DEVICES, BARRICADES, TEMPORARY PAVEMENT MARKINGS AND OTHER TRAFFIC CONTROL DEVICES SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE ITEM OF WORK "MINOR TRAF DEVICES."




ARBOR - PUBLIC SERVICES - ENGINEERING

2019 MISC UTILITY PROJECTS

ALTERNATE PEDESTRIAN ROUTE (APR) DETOUR

IG No.

ET No.



PARALLEL TO CURB

0.5 INCH MAXIMUM

0.25 INCH MAXIMUM

9 EDGE TREATMENT

LEADING EDGE –

#### SPECIFIC NOTES

- 1 CURB RAMPS SHALL BE 48" MIN. WIDTH WITH A FIRM, STABLE AND SLIP RESISTANT SURFACE.
- (2) PROTECTIVE EDGING WITH A 2" MIN. HEIGHT SHALL BE PLACED WHEN A CURB RAMP OR LANDING PLATFORM HAS A VERTICAL DROP OF 6" OR GREATER OR HAS A SIDE APRON SLOPE STEEPER THAN 1:3. PROTECTIVE EDGING SHOULD BE CONSIDERED WHEN CURB RAMPS OR LANDING PLATFORMS HAVE A VERTICAL DROP OF 3" OR MORE.
- (3) DETECTABLE EDGING WITH 6" MIN. HEIGHT AND CONTRASTING COLOR SHALL BE PLACED ON ALL CURB RAMP LANDINGS WHERE THE WALKWAY CHANGES DIRECTION (TURNS).
- 4 CURB RAMPS AND LANDINGS SHALL HAVE A 2% MAX. CROSS SLOPE.
- (5) CLEAR SPACE OF 48" x 48" MIN. SHALL BE PROVIDED ABOVE AND BELOW THE CURB RAMP.
- (6) THE CURB RAMP WALKWAY EDGE SHALL BE MARKED WITH A CONTRASTING COLOR, 2" TO 4" WIDE MARKING. THE MARKING IS OPTIONAL WHERE COLOR CONTRASTING EDGING IS USED.
- 7 WATER FLOW IN THE GUTTER SYSTEM SHALL NOT BE IMPEDED.
- 8 LATERAL JOINTS OR GAPS BETWEEN SURFACES SHALL BE LESS THAN 1/2" WIDTH.
- (9) CHANGES BETWEEN SURFACE HEIGHTS SHALL NOT EXCEED 1/2". LATERAL EDGES SHOULD BE VERTICAL UP TO 1/4" HIGH, AND BEVELED AT 1:2 BETWEEN 1/4" AND 1/2" HEIGHT.

#### SHOWN WITH PROTECTIVE EDGE

### SHOWN WITH SIDE APRON \_ ⑤ CLEAR SPACE (4) CROSS SLOPE 2% MAX. \_ (8) JOINT GAP TREATMENT \_\_\_ 9 EDGE TREATMENT \_\_\_ CURB FACE — 9 EDGE TREATMENT - 7 DRAINAGE 7 DRAINAGE PROTECTIVE EDGING 2" MIN. HEIGHT ABOVE RAMP SURFACE 2) PROTECTIVE EDGING 2" MIN. HEIGHT — ABOVE RAMP SURFACE -1 NON-SLIP SURFACE 4 CROSS SLOPE 2% MAX. 6 2" TO 4" WIDE EDGE MARKING · (5) CLEAR SPACE └─ ⑨ EDGE TREATMENT


**TEMPORARY CURB RAMP** PERPENDICULAR TO CURB



BYPASS ON ADJACENT AVAILABLE **RIGHT OF WAY** 


**BYPASS TYPE A** 

NOTE: MAY ONLY BE USED ON ROADWAY WITH POSTED SPEED OF 45 MPH OR LESS.



SIDEWALK BYPASS USING PARKING OR SHOULDER ON LOW SPEED ROADWAY

BYPASS TYPE B



SIDEWALK BYPASS USING SHOULDER OR PARKING LANE ON HIGH SPEED ROADWAY

BYPASS TYPE C

#### **GENERAL NOTES**

WHEN CLOSING OR RELOCATING CROSSWALKS OR SIDEWALKS, THE CONTRACTOR SHALL PROVIDE DETECTABLE TEMPORARY FACILITIES AND INCLUDE ACCESSIBILITY FEATURES CONSISTENT WITH EXISTING PEDESTRIAN FACILITIES.

TEMPORARY TRAFFIC CONTROL DEVICES FOR PEDESTRIANS ARE SHOWN. OTHER DEVICES MAY BE NECESSARY TO CONTROL VEHICULAR TRAFFIC. STAGE WORK, AS NECESSARY, TO PROVIDE AN ALTERNATE PEDESTRIAN ROUTE (APR) AT ALL TIMES. FOR ROADWAYS WITH NO AVAILABLE DETOURS, MAINTAIN ONE OPEN SIDEWALK AT ALL TIMES.

PROVIDE A SMOOTH, CONTINUOUS, HARD SURFACE THROUGH THE LENGTH OF THE APR. COMPACTED GRAVEL, AGGREGATE, OR SLAG MATERIALS ARE NOT ALLOWED. PROVIDE A FIRM, STABLE, AND SLIP RESISTANT TEMPORARY WALKWAY SURFACE TO COVER SHORT SEGMENTS OF ROUGH, SOFT, OR UNEVEN GROUND.

THE PEDESTRIAN TRAFFIC SIGNALS CONTROLLING CLOSED CROSSWALKS SHALL BE COVERED OR DEACTIVATED BY THE CITY OF ANN ARBOR. THE CONTRACTOR SHALL SCHEDULE AND COORDINATE THIS WORK WITH THE ENGINEER A MINIMUM OF 72 HOURS (NOT INCLUDING WEEKENDS & HOLIDAYS) PRIOR TO THE BEGINNING OF WORK THAT REQUIRES A SIDEWALK CLOSURE.

POST MOUNTED SIGNS LOCATED ADJACENT TO A SIDEWALK SHALL HAVE A 7 FOOT MINIMUM CLEARANCE FROM THE BOTTOM OF THE SIGN TO THE SIDEWALK SURFACE.


WHEN THE ENGINEER DETERMINES THAT THE CONTRACTOR'S OPERATIONS OR PLACEMENT OF TRAFFIC CONTROL DEVICES HAS CAUSED A SITUATION THAT THE VISIBILITY OF A TRAFFIC CONTROL DEVICE IS REDUCED ENOUGH TO CREATE A HAZARD, THE TRAFFIC CONTROL DEVICES SHALL BE DELINEATED WITH FLAGS OR OTHER ENGINEER-APPROVED DEVICES AT NO ADDITIONAL COST TO THE PROJECT.

MINIMIZE DISRUPTION TO PEDESTRIANS TO THE MAXIMUM EXTENT FEASIBLE BY PROVIDING AN APR IN THE FOLLOWING ORDER OF PREFERENCE:


- 1. PROVIDE THE APR ON THE SAME SIDE OF THE STREET AS THE DISRUPTED ROUTE
- 2. WHERE IT IS NOT FEASIBLE TO PROVIDE A SAME SIDE APR, PROVIDE A DETOUR ON THE OTHER SIDE OF THE STREET.
- 3. WHERE IT IS NOT FEASIBLE TO PROVIDE AN APR ON THE OTHER SIDE OF THE ROADWAY, PROVIDE AN APR DETOUR WITH TRAILBLAZING SIGNS AS SHOWN ON THE PROJECT PLANS.


#### SPECIFIC NOTES


- 1 TEMPORARY CURB RAMPS WITH DETECTABLE WARNINGS.
- (2) 5 DEVICE TAPER 25 FEET LONG, RECOMMENDED WHEN THE CLOSED AREA WAS USED AS AN INTERMITTENT TRAFFIC LANE OR BYPASS LANE. STREET PARKING SHALL BE PROHIBITED FOR AT LEAST 50 FEET IN ADVANCE OF THE MID-BLOCK CROSSWALK.
- (3) AN APPROVED AUDIBLE MESSAGE DEVICE OR TACTILE MESSAGE SHOULD BE PROVIDED FOR SIGHT-IMPAIRED PEDESTRIANS.
- (4) THE INTERNATIONAL SYMBOL OF ACCESSIBILITY SHALL BE DISPLAYED WHEN ANY WALKWAY THROUGH A WORK ZONE HAS BEEN DETERMINED TO BE TPAR COMPLIANT. THE SYMBOL OF ACCESSIBILITY SHALL NOT BE DISPLAYED IF PERSONS WITH DISABILITIES SHOULD NOT USE THE PRIMARY TEMPORARY PEDESTRIAN DETOUR. THE REASON FOR THE NON-COMPLIANCE SHALL BE POSTED AND AN ALTERNATE ROUTE SHALL BE POSTED WHEN THE PRIMARY TEMPORARY PEDESTRIAN DETOUR IS NON-COMPLIANT TO TPAR STANDARDS.
- (5) TYPICAL SIGN MESSAGE FOR A TEMPORARY PEDESTRIAN DETOUR SHALL INCLUDE INFORMATION SUCH AS THE DURATION OF THE WALKWAY RESTRICTIONS (BEGINNING AND/OR END DATES) AND A PROJECT CONTACT NUMBER FOR 24 / 7 QUESTIONS OR
- (6) SEE MMUTCD FOR GUIDANCE ON PLACEMENT AND USAGE OF BARRIER.




**PROJECT** UTILITY MISC 2019 ARBOR









CC	NSTRUCTION KEY							
KEY	DESCRIPTION							
НМА	SURFACE AREA FOR HMA							
CG	CONCRETE CURB OR CURB & GUTTER, ANY TYPE							
SW4	4" CONCRETE SIDEWALK							
SW6	6" CONCRETE SIDEWALK							
SW6-HE	6" CONCRETE SIDEWALK — HIGH EARLY							
SWR6	6" CONCRETE RAMP							
SWR6-HE	6" CONCRETE RAMP, DRIVE APPROACH— HIGH EARLY							
SW-RW1	INTEGRAL SIDEWALK RETAINING WALL, 6" TO 18"							
DOM	CONCRETE TYPE M DRIVE OPENING- HIGH EARLY							
DOL	CONCRETE TYPE L DRIVE OPENING- HIGH EARLY							
DWS	DETECTABLE WARNING, CAST IN PLACE							
ASC	ADJUST STRUCTURE COVER							
AB	ADJUST MONUMENT BOX OR GATE VALVE BOX							


CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING


SCALE PLAN: 1" = 20'


SCALE PLAN: 1" = 20'


BUCHOLZ CT


BUCHOLZ CT











CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING


CALE: 1"= 20

2019 MISC UTILITY PROJECTS

MAYWOOD AVENUE


MAYWOOD AVENUE







REMOVAL KEY										
KEY	DESCRIPTION									
1	REMOVE CONCRETE CURB OR CURB & GUTTER, ANY TYPE									
2	REMOVE CONCRETE SIDEWALK, RAMP AND DRIVES, ANY THICKNESS									
3	PAVT, REM *									
4	INLET FILTER									
5	PROTECTIVE FENCING									
6	TREE REMOVAL, 8" AND LARGER									
7	DR STRUCTURE, REM									


\*SAWCUT FULL DEPTH AT REMOVAL LIMITS





JHl	EL CITY OF ANN ARBOR - PUBLIC SEF	. PUBLIC SERVICES - ENGINEERING	ANA			
			OLTV OF ANN ABBOR			
	_   SCAI F · 1" = 20'					
Νο. <b>2</b> Ο	No.	2019 MISC UTILLLY PROJECTS	TOBLIC SERVICES 301 EAST HURON STREET			
F (		MAYWOOD AVENUE	P.O. BOX 8647 ANN ARBOR, MI 48107-8647			
31	DRAWING No.		734-794-6410 Www.a2gov.org	00	00 OUT FOR BID	3-1-19
	2018025-22	REMOVALS - STA. 8+00 - P.O.E.	CHIGH	REV.	DESCRIPTION	DATE



















	00	2	α	STA.		œ	2			_	6.					
		6+49 4"s		.:6+98 8"X 8" TEE	V											
			5 FT 8"W 8 In DI C	L 50	7+26 4"s					·						
	460 FT 8"W 8 In DI CL 50	FE   SI						8+, 4"	79 C	8+44 4"s			4"s ≬	1		
		STA.:6+48 LEAD	STA:6+68 LEAD		STA.: 7 LEAD		** ***		8+25 6"r			9+04    6"r	+11	9+53 4"s		
	6+15 1"g	6	3+59 1"g		7+23 STA:: 7+33 LEAD		MIN.	STA.		FT 8"W DI CL 50						
			2.50		1	(*)	7+76 12 <b>°</b> R	STA.: 7+94 LEAD STA.: 8+07		STA::8	STA:		•			
						7+44 1"g	7+66 1"g		(TO BE REMOVED)	101	:6+73		STA.: 7+	STA::		
						-		8+05 12"r	12" STORM SEWER (TO BE REMOVED)		8+72 1"g 'S' G'		53	9+53		
														9-	+67 "g '	
				V5 GVIV STA,			GRADE									
				V5 GVIW STA.:6+93 RIM:958.40			EXISTING GRADE									
-							Tf	RENCH DETAIL	TYPE I							<b>-</b>




















(	S.			Know what's	Call befo
				сс/рг/кв тн	DRAWN CHECKED
				3-1-19	DATE
				٥١	DESCRIPTION
				00 OUT FOR BID	REV.
	CITY OF ANN ARBOR	301 EAST HURON STREET	P.O. BOX 8647 ANN ARBOR, MI 48107-8647	734-794-6410 www.a2gov.org	
S ANN	COUNCED REAL	3BO	R	M.C. Brona ATE 0 4-5'	WCHIGA.
Y OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING		2019 MISC UTILLLY PROJECTS	MAYWOOD AVENUE		ROAD - SIA. 8+00 - P.O.E.
<b>CITY OF ANN ARBOR -</b>	• ☐ [V] S	No.		DRAWING No.	2018025-31
	3		F;	31	