

ADDENDUM No. 1

ITB No. 4586

Riverside Park Asphalt Path Renovations

Bids Due: June 12, 2019 by 2:00 P.M. (Local Time)

The information contained herein shall take precedence over the original documents and all previous addenda (if any), and is appended thereto. **This Addendum includes five (5) pages.**

Bidder is to acknowledge receipt of this Addendum No. 1, including all attachments (if any) in its Bid by so indicating on page ITB-1 of the Invitation to Bid Form. Bids submitted without acknowledgment of receipt of this addendum may be considered nonconforming.

The following forms provided within the ITB document must be included in submitted bids:

- City of Ann Arbor Prevailing Wage Declaration of Compliance
- City of Ann Arbor Living Wage Ordinance Declaration of Compliance
- Vendor Conflict of Interest Disclosure Form
- City of Ann Arbor Non-Discrimination Ordinance Declaration of Compliance

Bids that fail to provide these forms listed above upon bid opening will be rejected as non-responsive and will not be considered for award.

I. CORRECTIONS/ADDITIONS/DELETIONS

Changes to the Bid document which are outlined below are referenced to a page or Section in which they appear conspicuously. The Bidder is to take note in its review of the documents and include these changes as they may affect work or details in other areas not specifically referenced here.

Section/Page(s)

Change

BF-2 & BF-3

As provided in ITB No. 4586 Bid Document:
Bid Form, Section 1 – Schedule of Prices as Page BF-2 and BF-3

As updated herein:
Bid Form, Section 1 – Schedule of Prices as Pages BF-2 and BF-3.

Comment: The intent with this change is to simply replace the inaccurate Page BF-2 and BF-3 provided in the ITB Document with the accurate Page BF-2 and BF-3 provided herein. Specifically, note clarifications on the disposition of items removed to Items 4 and 5 on both pages. Please use these updated bid forms found herein in your bid response.

II. QUESTIONS AND ANSWERS

The following Questions have been received by the City. Responses are being provided in accordance with the terms of the ITB. Bidders are directed to take note in their review of the documents of the following questions and City responses as they affect work or details in other areas not specifically referenced here.

Question 1: Will a copy of the attendance sheet of the pre-bid meeting that happened June 3rd at 11:00am be made available?

Answer 1: Yes, see the Pre-Bid Sign-In Sheet attached hereto.

Bidders are responsible for any conclusions that they may draw from the information contained in the Addendum.

PATH RENOVATION OPTION A BID ITEMS

The Bidder agrees to complete the Project and all related work, as specified for the following unit prices.

BID OPTION A: PULVERIZE EXISTING HMA IN PLACE AND INSTALL NEW HMA PATH					
Item	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
1.	General Conditions, Mobilization, Bonds, Insurance, Permits	1	LS	\$	\$
2.	Install temporary path closure fencing and tree protection fencing.	1	LS	\$	\$
3.	Installation and management of all Soil Erosion and Sedimentation Control measures	1	LS	\$	\$
4.	Full removal of vegetation, roots, and stumps along areas to accommodate proposed work. Removed materials to be lawfully disposed off site.	1	LS	\$	\$
5.	Removal of existing benches, picnic tables, posts and concrete pads per plan. Memorial plaques on benches to be salvaged. All other removed materials to be lawfully disposed off site.	1	LS	\$	\$
6.	Pulverization of existing asphalt path surfacing (approximately 9' wide), grading and compaction for use as base aggregate. Final milling product should be no greater than 1 ½" in diameter. Prepare and compact existing subbase of path alignment, installation of milling material to 6" depth, load, haul, place, and compact in place	1,700	LF	\$	\$
7.	Excavation of existing soils and grading to widen path to 10' wide HMA and 12' wide base aggregate. Excavated materials to be removed from site and lawfully disposed.	600	SY	\$	\$
8.	Limestone for widening pathway base to 12' – 21AA, 6" depth. (Expanding path base by 3')	600	SY	\$	\$
9.	Bituminous Hot Mix Asphalt Leveling course – LVSP	220	TON	\$	\$
10.	Bituminous Hot Mix Asphalt Wearing course – 5E1	220	TON	\$	\$
11.	Provide and install three (3) picnic tables and four (4) benches with concrete pads per standard details. Locations to be determined in field by supervising professional.	1	LS	\$	\$
12.	Restoration, topsoil, seed and mulch all disturbed areas. Site Clean-up for entire project.	1	LS	\$	\$
13.	Certified payroll compliance & reporting	1	LS	\$	\$
Estimated Total Bid Amount (Items 1 through 13)					\$

PATH RENOVATION OPTION B BID ITEMS

The Bidder agrees to complete the Project and all related work, as specified for the following unit prices.

BID OPTION B: INSTALL NEW HMA PATH AND NEW PATH BASE					
Item	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
1.	General Conditions, Mobilization, Bonds, Insurance, Permits	1	LS	\$	\$
2.	Install temporary path closure fencing and tree protection fencing	1	LS	\$	\$
3.	Installation and management of all Soil Erosion and Sedimentation Control measures	1	LS	\$	\$
4.	Full removal of vegetation, roots, and stumps along areas to accommodate proposed work. Removed materials to be lawfully disposed off site.	1	LS	\$	\$
5.	Removal of existing benches, picnic tables, posts and concrete pads per plan. Memorial plaques on benches to be salvaged. All other removed materials to be lawfully disposed off site.	1	LS	\$	\$
6.	Demolition, removal, and lawful disposal of all existing asphalt paths – approximately 9' wide.	1,700	LF	\$	\$
7.	Excavation, loading, hauling, and grading of existing soils to accommodate proposed 12' wide base aggregate for path. Excavated materials to be removed from site and lawfully disposed.	2,400	SY	\$	\$
8.	Structural Geogrid placed below limestone base	2,400	SY	\$	\$
9.	Limestone for pathway base – 21AA, 6" depth	2,400	SY	\$	\$
10.	Bituminous Hot Mix Asphalt Leveling course – LVSP	220	TON	\$	\$
11.	Bituminous Hot Mix Asphalt Wearing course – 5E1	220	TON	\$	\$
12.	Undercut allowance – geotextile and 21AA Limestone compacted	250	CY	\$	\$
13.	Undercut allowance – geotextile and 6A Limestone compacted	250	CY	\$	\$
14.	Provide and install three (3) picnic tables and four (4) benches with concrete pads per standard details. Locations to be determined in field by supervising professional.	1	LS	\$	\$
15.	Restoration, topsoil, seed and mulch all disturbed areas; Site Clean-up for entire project.	1	LS	\$	\$
16.	Certified payroll compliance & reporting	1	LS	\$	\$
	Estimated Total Bid Amount (Items 1 through 16)				\$

