

CITY OF ANN ARBOR ENGINEERING

RESEARCH PARK DRIVE

SHEET LIST TABLE SHEET TITLE LEGEND 3 OVERALL PLAN HORIZONTAL ALIGNMENT TYPICAL SECTIONS **SOIL EROSION & SEDIMENTATION CONTROL PAVEMENT CORES LOGS** REMOVALS ROAD PLAN & PROFILES DETAIL GRADES PAVEMENT MARKING PLAN MAINTENANCE OF TRAFFIC SPECIAL DETAILS

BID No. 23-10, FILE No. 2022-035

MICHIGAN DEPARTMENT OF TRANSPORTATION (MDOT) STANDARD PLANS

WHERE THE FOLLOWING ITEMS ARE CALLED FOR ON PLANS, THEY ARE TO BE CONSTRUCTED ACCORDING TO THE MDOT STANDARD PLANS GIVEN BELOW.


ROAD STANDARD PLANS

SEEDING AND TREE PLANTING * TRAFFIC AND SAFETY STANDARD PLANS

WZD-100-A GROUND DRIVEN SIGN SUPPORTS FOR TEMP SIGNS *

WZD-125-E TEMPORARY TRAFFIC CONTROL DEVICES *

* = SPECIAL DETAILS



PUBLIC ACT 174 OF 2013, THE CONTRACTOR SHALL CALL 811 OR THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF

ELECTRICAL POWER, CABLE TV AND FIBER OPTIC LINES ARE APPROXIMATE. THE CITY OF ANN ARBOR ASSUMES NO RESPONSIBILITY FOR THEIR ACCURATE REPRESENTATION IN THIS DRAWING. MISS DIG MUST

AASHTO, THE 2020 EDITION OF THE MDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION, IT'S DETAILS, AND THIS PROJECT'S CONTRACT DOCUMENTS. THE OMISSION OF ANY CURRENT STANDARD DETAIL DOES NOT RELIEVE THE CONTRACTOR FROM THIS REQUIREMENT.




DRIV

02 / 21 / 2023

PREPARED UNDER THE SUPERVISION OF

JEREMY SCHROT, P.E. PROJECT MANAGER



W	WATER MAIN
R	WATER MAIN STORM SEWER
s	SANITARY SEWER
——F0———	FIBER OPTIC
——E	ELECTRICAL
-	CENTERLINE OF DITCH
	CENTERLINE OF ROAD
////	FENCE
:::	GRAVEL
	SILT FENCE
	PROTECTIVE FENCE
. • • • • • • • •	GUARDRAIL
	LOT/UNIT
	CURB
	TEMPORARY GRADING PERMIT
800 ———	CONTOUR MAJOR
799	CONTOUR MINOR
	WATER EASMENT
	STORM EASEMENT
	SANITARY EASEMENT
	R.O.W.
	LIMITS OF CONSTRUCTION
	LIMIT OF GRADING
	STONE WALL
1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	DETECTABLE WARNING
	ASPHALT
	CONCRETE
A	SIDEWALK
	TREE (DECIDUOUS)
	TREE (CONIFEROUS)
	TREE TO BE REMOVED (DECIDUOUS)
	TREE TO BE REMOVED (CONIFEROUS)
	STUMP TO BE REMOVED

CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

SCALE: NTS

IMPROVEMENTS PROJECT

SHEET No.

CONSTRUCTION NOTES:

- 1. Driveways and entrances to buildings, real estate property, and the like shall not be blocked except for short durations and only when approved by the Engineer. Vehicular and pedestrian access shall be maintained at all times. It shall be the Contractor's responsibility to coordinate all necessary driveway closures with the property owner(s) and resident(s) in the areas of construction.
- 2. The location and depth of all existing utilities and service leads are to be field verified by the Contractor prior to
- 3. Location and depth of utilities as depicted on the plans is approximate and shown according to the best information available. It is the Contractor's responsibility to excavate ahead and adjust depth of conflict utilities accordingly. Any damage to utilities is the Contractor's responsibility to avoid and/or repair as necessary.
- 4. The Contractor is to take special care to protect the existing water main and be responsible for maintaining consistent water service.
- 5. During non-working hours no trench shall remain open; any open trench shall be properly secured with protective fencing. This work will not be paid for separately, but shall be included in "General Conditions, Max \$_".
- 6. Trenches for new water services shall be excavated to MIOSHA and City of Ann Arbor Public Works requirements.
- 7. City of Ann Arbor Public Works will install the corporation and copper service lead(s) to transfer the connection(s). If an existing water service is found to be failing or is not copper, the lead will be replaced to the curb box by Public
- 8. For the installation of corporations, or any other related activities, the Contractor shall not receive additional compensation for delays due to the scheduling of or coordination with the City of Ann Arbor Public Works.
- 9. "No Parking" signs shall be installed by the Contractor at locations as approved or directed by the Engineer. All signs shall be installed in accordance with the detailed specifications.
- 10. Postal delivery and refuse pickup service shall be maintained at all times by the Contractor.
- 11. Where street curbs are undermined due to construction activities, they shall be removed and replaced as directed by the Engineer.
- 12. The Contractor shall be responsible for the continuous maintenance of the temporary road surface and soil erosion control measures within the construction area until the full completion of the project. This work will not be paid for separately, but shall be included in "General Conditions, Max \$_".
- 13. All curb, sidewalk, driveway approach removals shall be approved by Engineer before the work is done.
- 14. Sawed sewer pipe connections shall be coupled with a Fernco flexible coupling and a stainless steel shear ring.
- 15. The location of material stock piles and on—site staging areas to be approved by the Engineer.
- 16. For mainline paving, the width of the mat for each pass of the paver shall be not less than 10.5' or greater than 15', as directed by the Engineer. The Engineer will direct the layout of the longitudinal joints during construction.
- 17. All structures shall receive new castings as directed by the Engineer, as specified on the standard casting schedule. The existing castings are the property of the City of Ann Arbor. The Contractor shall deliver to City of Ann Arbor Public Works Facility at the W.R. Wheeler Service Center located at 4251 Stone School Road.
- 18. Payment for drainage structure sumps, where specified, shall be included in the payment for the various drainage structure sizes and or types.
- 19. Where sewer and water main are to be removed & replaced or added, all pipe shall be installed using Trench Detail detailed in the specifications or shown on Plans. Backfill for sewer and water construction shall be MDOT Granular Material, Class II, Modified.
- 20. Existing street name, guide, and regulatory signs, and mailboxes which conflict with the proposed construction shall be removed prior to construction, stored in a manner which will prevent damage, and re—set in locations as directed by the Engineer. This work will not be paid for separately, but shall be included in "Machine Grading, Modified"
- 21. In areas where edge drain cannot be installed in accordance with City of Ann Arbor Detail SD-TD-11, the edge drain shall be installed at the depth as indicated on the plans, or as directed by Engineer. In no case shall the edge drain be installed at a grade less than 0.50% or at a depth of less than 2' below top of proposed pavement.
- 22. Maintenance gravel in driveway openings can be substituted with HMA millings compacted and free of any items that could cause damage to vehicles. This work will not be paid for separately, but shall be included in "General Conditions,

PERMITS REQUIRED TO BE OBTAINED BY THE CONTRACTOR PRIOR TO THE REGINNING OF CONSTRUCTION

LANE CLOSURE PERMIT*	CITY OF ANN ARBOR ENGINEERING
"NO PARKING" SIGNS PERMIT*	CITY OF ANN ARBOR ENGINEERING
GRADING/SOIL EROSION & SEDIMENTATION CONTROL PERMIT*	CITY OF ANN ARBOR CUSTOMER SERVICE
RIGHT-OF-WAY PERMIT*	CITY OF ANN ARBOR CUSTOMER SERVICE

PERMITS REQUIRED TO BE OBTAINED BY THE CITY OF ANN ARBOR PRIOR TO THE BEGINNING OF CONSTRUCTION.

PERMIT	ISSUING AUTHORITY

CONTACT	INFORMATION	
		•


PHONE

PUBLIC UTILITIES	OWNER	CONTACT
WATER SANITARY	CITY OF ANN ARBOR PUBLIC WORKS	(734) 794–6350
FORESTRY	W.R. WHEELER SERVICE CENTER 4251 STONE SCHOOL ROAD ANN ARBOR, MI 48108	
SIGNS SIGNALS STREET LIGHTS		MARK MORENO (734) 794-6361
PRIVATE UTILITIES	OWNER	CONTACT
GAS	DTE ENERGY	RUSSELL THORNTON 1(800) 338-0178
CABLE	COMCAST	CAMILLA DEAN (419) 874-9262
PHONE	AT&T	ARTHUR MADISON (586)214-7753
FIBER	WESTERN TELECOM	HEATHER SHAWL (616) 393-0138
FIBER OPTIC	ACD NET	JACOB LAPE (517) 999-3276

RONALD KOCIENSKI

RONALD.KOCIENSKI@VERIZON.COM

VERIZON








- PUBLIC SERVICES - ENGINEERING
RESEARCH PARK DRIVI


CITY OF ANN ARBOR


SHEET No.

















NOTIFY THE CITY OF ANN ARBOR SOIL EROSION CONTROL OFFICE 48 HOURS PRIOR TO BEGINNING WORK ON THE PROJECT. PHONE: 734-794-6265.

- 1. THE CONTRACTOR SHALL IMPLEMENT AND MAINTAIN THE SOIL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER AT ALL TIMES DURING CONSTRUCTION. ANY MODIFICATIONS OR ADDITIONS TO THE SOIL EROSION CONTROL MEASURES DUE TO CONSTRUCTION OR CHANGED CONDITIONS SHALL BE AS DIRECTED AND APPROVED BY THE ENGINEER.
- 2. ALL SOIL EROSION AND SEDIMENTATION CONTROL WORK SHALL CONFORM TO THE PERMIT REQUIREMENTS OF THE CITY OF ANN ARBOR. THE LAWS OF THE STATE OF MICHIGAN, AND THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
- 3. DAILY, OR AFTER ANY STORM EVENT, INSPECTIONS OF EROSION CONTROL MEASURES SHALL BE MADE BY THE CONTRACTOR. PERIODIC INSPECTIONS MAY BE MADE BY THE ENGINEER TO DETERMINE THE EFFECTIVENESS OF EROSION AND SEDIMENTATION CONTROL MEASURES. ANY NECESSARY CORRECTIONS SHALL BE MADE WITHOUT DELAY, AND WITHOUT ADDITIONAL COST TO THE CITY OF ANN ARBOR.
- 4. EROSION AND SEDIMENTATION FROM WORK ON THE SITE SHALL BE CONTAINED ON THE SITE AND NOT BE ALLOWED TO COLLECT ON ANY OFF-SITE AREAS, ROADWAYS OR WATERWAYS.
- 5. ALL MUD/SOIL TRACKED ONTO ROADWAYS FROM THE SITE DUE TO CONSTRUCTION. SHALL BE PROMPTLY REMOVED BY THE CONTRACTOR. IF SO ORDERED, THE CONTRACTOR SHALL PROVIDE AND OPERATE A VACUUM-TYPE STREET SWEEPER, AT NO ADDITIONAL COST TO THE CITY OF ANN ARBOR.
- 6. RESTORATION OF ALL DISTURBED AREAS, INCLUDING PLACEMENT OF TOPSOIL, SEED, FERTILIZER AND MULCH AND/OR SOD SHALL BE PERFORMED WITHIN FIVE (5) DAYS OF THE COMPLETION OF FINAL GRADE.
- 7. CONSTRUCTION OPERATIONS SHALL BE SCHEDULED AND PERFORMED SO THAT PREVENTATIVE SOIL EROSION CONTROL MEASURES ARE IN PLACE PRIOR TO EXCAVATION IN CRITICAL AREAS AND TEMPORARY STABILIZATION MEASURES ARE IN PLACE IMMEDIATELY FOLLOWING BACKFILLING OPERATIONS.
- 8. SPECIAL PRECAUTIONS WILL BE TAKEN IN THE USE OF CONSTRUCTION EQUIPMENT TO PREVENT SITUATIONS THAT PROMOTE EROSION.
- 9. PROPER DUST CONTROL SHALL BE MAINTAINED DURING CONSTRUCTION BY USE OF

WATER TRUCKS AND/OR OTHER METHODS APPROVED BY THE ENGINEER.

- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY SOIL EROSION CONTROL MEASURES AND REMOVAL OF SOME MEASURES UPON AUTHORIZED COMPLETION OF THE PROJECT. FINAL COMPLETION OF PROJECT WILL NOT BE AUTHORIZED UNTIL ALL SITE WORK AND UTILITY CONSTRUCTION IS COMPLETE AND ALL SOILS ARE STABILIZED.
- 11. THE CONTRACTOR SHALL NOT GRADE INTO ADJACENT PROPERTIES. SILT AND PROTECTIVE FENCE SHALL BE INSTALLED AND MAINTAINED TO PREVENT GRADING, EROSION AND SEDIMENTATION INTO THE ADJACENT PROPERTIES.
- 12. TREE PROTECTION FENCING MUST REMAIN INTACT UNTIL RESTORATION OF THE SITE IS COMPLETE.

SEQUENCE OF EROSION CONTROL MEASURES:

1. THE CONTRACTOR IS TO SUBMIT TO THE ENGINEER, A SEQUENCE OF CONSTRUCTION WITH RESPECT TO THE SOIL EROSION CONTROL MEASURES FOR REVIEW, COMMENT AND APPROVAL. THIS SCHEDULE IS TO INCLUDE INSPECTION AND REPAIR OF ALL TEMPORARY EROSION CONTROL MEASURES DAILY AND WITHIN 24 HOURS OF A STORM EVENT.

SAMPLE SOIL EROSION AND SEDIMENTATION CONTROL INSTALLATION MINIMUM

- <u>REQUIREMENTS:</u> 1.1. INSTALL SILT FENCE, TREE PROTECTION FENCING, MUD MATS, INLET FILTERS ON EXISTING DRAINAGE FEATURES, AND ALL OTHER TEMPORARY SOIL EROSION CONTROLS, PRIOR TO ANY CLEARING OR EARTH MOVING OPERATION.
- 1.2. STRIP AND STOCKPILE TOPSOIL. STABILIZE STOCKPILE AS REQUIRED.
- 1.3. INSTALL WATER MAINS. STORM AND SANITARY SEWERS. AND OTHER ENCLOSED DRAINAGE FEATURES. NEW INLET FILTERS SHALL BE INSTALLED IMMEDIATELY FOLLOWING INSTALLATION OF NEW DRAINAGE INLETS.
- 1.4. PERFORM MACHINE GRADING OPERATIONS AND CONSTRUCT PAVEMENTS (MAINLINE, SIDEWALKS, DRIVES, ETC.).
- 1.5. CONTINUALLY MAINTAIN EROSION AND SEDIMENTATION CONTROL MEASURES, AS REQUIRED TO ALLOW DRAINAGE AND SEDIMENT REMOVAL. REMOVE ANY ACCUMULATED SEDIMENT IMMEDIATELY.
- 1.6. COMPLETE ALL FINE GRADING.

- 1.7. TEMPORARY SEED AND INSTALL EROSION CONTROL BLANKET IN ALL DISTURBED AREAS.
- 1.8. REFER TO LANDSCAPE PLANTING PLANS FOR PERMANENT SITE STABILIZATION.
- 1.9. CLEAN OUT STORM SEWER SYSTEMS.
- 1.10. REMEDY ANY NOTED DEFECTS TO THE SATISFACTION OF THE CITY OF ANN ARBOR'S SOIL EROSION AND SEDIMENTATION CONTROL OFFICIAL.
- 1.11. ALL TEMP. SOIL EROSION CONTROL MEASURES MUST BE REMOVED, WITH ENGINEERS APPROVAL, PRIOR TO FINAL INSPECTION

NOTE: THIS SEQUENCE IS FOR INFORMATION ONLY. IT IS INTENDED TO SHOW THE SEQUENCE OF CONSTRUCTION WITH RESPECT TO THE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES. THE CONTRACTOR IS RESPONSIBLE FOR SUBMITTING THEIR OWN DETAILED CONSTRUCTION SEQUENCE AND SCHEDULE TO THE ENGINEER FOR REVIEW, COMMENT, AND APPROVAL.

TEMPORARY SEEDING:

- 1. SEED IN ACCORDANCE WITH PROJECT DRAWINGS AND SPECIFICATIONS.
- 2. ANY DISTURBED AREA NOT PAVED, SEEDED, MULCHED, SODDED OR BUILT UPON BY NOVEMBER 15TH OR JUNE 30TH IS TO BE TEMPORARILY STABILIZED PER SPECIFICATIONS.

THE ESTIMATED COST OF SOIL EROSION AND SEDIMENTATION CONTROL MEASURES. TOPSOIL, SEEDING, AND MULCH = \$52,200.

ESTIMATE OF EXCAVATION AND FILL FROM EXISTING TO FINAL GRADE:


• EXCAVATION = 9,660 CY, FILL = 90 CY

ON SITE SOILS PER THE USDA SOIL SURVEY OF WASHTENAW COUNTY, MICHIGAN:

- BbB BLOUNT LOAM 2% TO 6% SLOPES.
- CpA CONOVER BROOKSTON LOAMS 0% TO 2% SLOPES
- Pe PEWAMO CLAY LOAM 0% TO 2% SLOPES
- StB ST. CLAIR CLAY LOAM, 2% TO 6% SLOPES
- WaA WAWASEE LAOM, 2% TO 6% SLOPES

IMPERVIOUS PROJECT AREA PRIOR TO CONSTRUCTION POST CONSTRUCTION = 6.62 ACRES = 6.63 ACRES

AREA OF PROPOSED DISTURBANCE = 6.97 ACRES



SILTSACK DETAIL

NOTE: THE SILTSACK WILL BE MANUFACTURED FROM A WOVEN POLYPROPYLENE FABRIC THAT MEETS OR EXCEEDS THE FOLLOWING SPECIFICATIONS.

REGULAR FLOW SILTSACK

(FOR AREAS OF LOW TO MODERATE PRECIPITATION AND RUN-OFF)

RAB TENSILE STRENGTH ASTM D-4632 300 LBS RAB TENSILE ELONGATION ASTM D-4632 20% JINCTURE ASTM D-4833 120 LBS JILLEN BURST ASTM D-3786 800 PSI RAPEZOID TEAR ASTM D-4533 120 LBS V RESISTANCE ASTM D-4355 80% PPARENT OPENING SIZE ASTM D-4751 40 US SIEVE	TEST METHOD	REQUIRED VALUE	<u>PROPERTIES</u>
OW RATE ASTM D-4491 40 GAL/MIN/SQ FT ERMITTIVITY ASTM D-4491 0.55 SEC -1	20% 120 LBS 800 PSI 120 LBS 80% 40 US SIEVE 40 GAL/MIN/SQ	ASTM D-4632 ASTM D-4833 ASTM D-3786 ASTM D-4533 ASTM D-4355 ASTM D-4751 ASTM D-4491	RAB TENSILE ELONGATION JNCTURE JLLEN BURST RAPEZOID TEAR V RESISTANCE PPARENT OPENING SIZE LOW RATE

HI-FLOW SILTSACK


(FOR AREAS OF MODERATE TO HEAVY PRECIPITATION AND RUN-OFF)

TON ANEXO OF MODERATE TO THE	EATT TREGITTATION F	THE ROLL OIL)
<u>PROPERTIES</u>	REQUIRED VALUE	TEST METHOD
GRAB TENSILE STRENGTH GRAB TENSILE ELONGATION PUNCTURE MULLEN BURST TRAPEZOID TEAR UV RESISTANCE APPARENT OPENING SIZE FLOW RATE PERMITTIVITY	ASTM D-4632 ASTM D-4632 ASTM D-4833 ASTM D-3786 ASTM D-4533 ASTM D-4535 ASTM D-4751 ASTM D-4491 ASTM D-4491	

OIL-ABSORBANT SILTSACK


(FOR AREAS WHERE THERE IS A CONCERN FOR OIL RUN-OFF OR SPILLS)

IT IS THE INTENT OF THE PLANS AND SPECIFICATIONS THAT THE CONTRACTOR INSTALL THE REBAR AS SHOWN IN THIS DETAIL TO PROVIDE A FULLY FUNCTIONING UNIT. ALL COSTS ASSOCIATED WITH FURNISHING, CLEANING AS MANY TIMES AS REQUIRED, DISPOSAL OF SEDIMENT, AND REMOVING THE INLET FILTER WHEN NO LONGER NEEDED IS INCLUDED IN THE ITEM OF WORK AND WILL NOT BE PAID FOR SEPARATELY.



MULCH BLANKET DETAIL

APPLIES TO ALL AREAS TO BE PERMANENTLY RESTORED WITH GRASS. SEE LANDSCAPE PLANS FOR MORE DETAILS.





DRIV

ANN ARBOR

SHEET No.



Testing Engineers & Consultants, Inc.

1343 Rochester Road - PO Box 249 - Troy, Michigan - 48099-0249
(248) 588-6200 or (313) T-E-S-T-I-N-G
Fax (248) 588-6232

Boring N	lo.: RP-1		Job No.: 62011	Project: Research Park Dri East of S. State Street	ve, Northwes	st of Ellsw	orth 8
Client: C	ity of Ann	Arbor					
Type of I	Rig: Truck			Location: Ann Arbor, Michi	gan		
33	Method: So		Augers	Drilled By: R. Favor			
	Surface Ele		200 Branser	Started: 8/30/2021			
Ground	Surface Lit	avation.		Completed: 8/30/2021			
Depth	Sample	N	Strata	Soil Classification	w	d	9

	Method: So Surface Ele			Started: 8/30/2021 Completed: 8/30/2021			
Depth (ft)	Sample Type	N	Strata Change	Soil Classification	w	d	qu
2.5	LS	8 14 24	,31 1	ASPHALT (3 3/4") Moist Brown Fine SAND With Trace Of Gravel-Possible Fill (8	8.7		
5.0	LS	8 11 13	5	Compact Moist Brown Fine SAND With Trace Of Gravel & Clay Layers	16.9	124	
7.5				Medium Compact Wet Brown Fine SAND With Trace Of Gravel Bottom of Boring at 5'			
10.0							
12.5							
15.0							
17.5							
20.0							
22.5							
SS - 2" 1	dard Penetration D. Split Spoon Itional Liner San Iby Tube Samp er Sample	Sample	ce w - H2O, d - Bulk qu - Uncc DP - Dire RC - Roc	% of dry weight Water Enco Density, pcf unfined Compression, tsf ct Push k Core Boring No.	ion: Cave		i.



Testing Engineers & Consultants, Inc.

1343 Rochester Road - PO Box 249 - Troy, Michigan - 48099-0249
(248) 588-6200 or (313) T-E-S-T-I-N-G
Fax (248) 588-6232

(0.0)	Rig: Truck Method: So	lid Stem	Augers	Drilled By: R. Favor			
	Surface Ele			Started: 8/30/2021			
				Completed: 8/30/2021			
Depth (ft)	Sample Type	N	Strata Change	Soil Classification	w	d	qu
			.42 1.25	\ASPIIALT (FI)			
-	LS	7 5	1.25	ASPHALT (5")	3.1		
2.5		5	3.33	Moist Dark Brown Fine SAND With Trace Of Gravel & Clay-Possible Fill			
	LS	3		Loose Moist Brown Fine SAND With Trace Of Gravel	4.5		
5.0		2	5	Very Loose Moist Brown Fine SAND With Trace Of Gravel			
-				11 10 10 10 10 10 10 10 10 10 10 10 10 1			
7.5				Bottom of Boring at 5'			
51							
10.0							
5							
12.5 -							
15.0 -							
-							
17.5							
-							
20.0							
20.0-							
2 2 2 2 3							
22.5							
_							



Testing Engineers & Consultants, Inc. 1343 Rochester Road - PO Box 249 - Troy, Michigan - 48099-0249 (248) 588-6200 or (313) T-E-S-T-I-N-G Fax (248) 588-6232

Boring I	No.: RP-3		Job No.:	62011	Project: Research Park Drive East of S. State Street	, Northwes	t of Ellsw	orth
Client: (City of Ann	Arbor			A STORM WAR TO STORM AND A STO			
Type of	Rig: Truck				Location: Ann Arbor, Michiga	in		
Drilling	Method: So	olid Ster	n Augers		Drilled By: R. Favor			
Ground	Surface El	evation	:		Started: 8/30/2021			
					Completed: 8/30/2021			T
Depth (ft)	Sample Type	N	Strata Change	Soil Classific	ation	w	d	79
-		-	.25 1.17	ASPHALT (3")	1			
	LS	9 16	1000	MOPHALI (3)		6.4		
2.5		28		Moist Brown Fine SAND With Some Clay-Possible Fill	e Gravel & Trace Of			
-	LS	13		Non-transfer of the state of th	and the statement of	3.7		
5.0-	ः स्तातिस	23 25	5	Compact Moist Brown Fine SAND V	Vith Trace Of Gravel	597.0 N.		
ESKO.				Bottom of Boring at 5'				
				Estation soming at a				
7.5								
10.0								
10 MANUAL								
12.5								
15.0								
-								
47.5								
17.5								
20.0								
20.5								
22.5								
"N" - Star	ndard Penetrati	on Resistar	nce w-H2O,	% of dry weight	Water Enc	ountered:	None	L
ST - She	D. Split Spoon tional Liner Sar iby Tube Samp	sample mple ole	qu - Unco DP - Dire	Density, pcf Infined Compression, tsf It Push	At Comple	tion: None		
AS - Aug	er Sample		RC - Roc	c Core	Boring No.	RP-3		

Boring No. RP-3



Job No.: 62011

"N" - Standard Penetration Resistance
SS - 2"),D. Split Spoon Sample
LS - Sectional Liner Sample
ST - Shelby Tube Sample
AS - Auger Sample

W - H2O, % of dry weight
d - Bulk Density, pcf
qu - Unconfined Compression, tsf
DP - Direct Push
RC - Rock Core

Boring No. RP-1

Project: Research Park Drive, Northwest of Ellsworth & East of S. State Street

Water Encountered: None At Completion: None Boring No. RP-4

Testing Engineers & Consultants, Inc. 1343 Rochester Road - PO Box 249 - Troy, Michigan - 48099-0249 (248) 588-6200 or (313) T-E-S-T-I-N-G Fax (248) 588-6232

2W 0 2	2 22	1000		Last of 3, State Street			
	ity of Ann			Location: Ann Arbor, Michigan	i		
	Rig: Truck			Drilled By: R. Favor	71.		
	Method: So			Started: 8/30/2021			
Ground	Surface Ele	evation:		Completed: 8/30/2021			
	2		la. I				ľ
Depth (ft)	Sample Type	N	Strata Change	Soil Classification	w	d	qu
			.35	\			
-	LS	6 14	1.42	\ASPHALT (4 1/4")	4.8		
2.5-		18		Moist Brown Fine SAND & Gravel With Trace Of Clay-Possible Fill			
1	LS	6		Compact Moist Brown Fine SAND With Some Gravel	4.5		
5.0-		17 23	5	Compact Worst Brown Fine SAND With Some Graver			
500				Bottom of Boring at 5'			
7.5 -							
7.0							
-							
10.0							
12.5							
3							
15.0							
3							
17.5							
20.0							
-							
22.5							
-							
1							



Job No.: 62011

Boring No.: RP-5

Client: City of Ann Arbor


Boring No. RP-2

Project: Research Park Drive, Northwest of Ellsworth & East of S. State Street

Testing Engineers & Consultants, Inc.

1343 Rochester Road - PO Box 249 - Troy, Michigan - 48099-0249
(248) 588-6200 or (313) T-E-S-T-I-N-G
Fax (248) 588-6232

				Completed: 8/30/2021						
Depth (ft)	Sample Type	N	Strata Change	Soil Classification	w	d	qu			
			.38	ASSELLALT (A 4/2")						
-	LS	12 20		ASPHALT (4 1/2")	3.6					
2.5-		21	3.5	Compact Moist Brown Fine SAND With Some Gravel						
-	LS	9	85080	W. F. C. W. W. F. C. CAND WILL CO. C. J.	6.3					
5.0-		10	5	Medium Compact Moist Brown Fine SAND With Some Gravel						
-				Bottom of Boring at 5'						
7.5										
-										
10.0										
A.4884										
12.5										
12.5										
00000000										
15.0 -										
5										
17.5										
1										
20.0										
100										
22.5-										
- 3										







CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING


SCALE: NTS


IMPROVEMENTS PROJECT


IMPROVEMENTS PROJECT



















SHEET No. 21 OF 41




CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING


SCALE PLAN: 1"= 40" HORIZ


T = 5" VERT

IMPROVEMENTS PROJECT

INCOMMOS NO 22 OF 41








CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

| SCALE PLAN: 1"= 40' HORIZ
| SCALE PLAN: 1"= 40' HORIZ
| The servent is a servent in the 25 OF 41




CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

SCALE PLAN: 1" = 40' PROFILE: 1" = 5' VERT

TITE S. VERT

INPROVEMENTS PROJECT 26 OF 41



820.93 820.93

821.42 821.42

821.29 821.29

821.23 821.23

99+75 100+00 +25 +50 +75 **101+00** +25 +50 +75 **102+00** +25

820.84 820.84

819.68

+⁷⁵ **104+00** +²⁵

819.80 **819.80**

819.91

+50

820.17

+75 **103+00** +25

+50


819.54

+50

819.33 **819.33**

819.31

+⁷⁵ 105+00 +²⁵ 105+50





CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING


SCALE PLAN: 1" = 40' PROFILE: 1" = 40' HORIZ


TITES VERT


IMPROVEMENTS PROJECT






































BARRICADE, TYPE III, HIGH INTENSITY, DOUBLE SIDED, LIGHTED

CHANNELIZING DEVICE @ 50' SPACING UNLESS NOTED OTHERWISE

NOTES: MAINTAIN ACCESS TO DRIVEWAYS AT ALL TIMES AS DIRECTED BY

SIGNS PLACED AT 100' SPACING. ADJUST AS NECESSARY TO FIT FIELD

	Size	Area (Sft)	Total						
Sign Code			Stages 1 & 1A		Stages 2 & 2A		Project		
			Quantity	Area (Sft)	Quantity	Area (Sft)	Quantity	Area (Sft)	
*D3-1	42 x 10	2.92	2	5.83	2	5.83	2	5.83	
G20-2	36 x 18	4.50	1	4.50	1	4.50	1	4.50	
M4-10(L)	48 x 18	6.00	0	0.00	1	6.00	1	6.00	
M4-10(R)	48 x 18	6.00	2	12.00	0	0.00	2	12.00	
M4-9(L)	30 x 24	5.00	0	0.00	0	0.00	0	0.00	
M4-9(R)	30 x 24	5.00	1	5.00	0	0.00	1	5.00	
M4-9(S)	30 x 24	5.00	2	10.00	3	20.00	3	15.00	
R1-1	30 x 30	6.25	1	6.25	0	0.00	1	6.25	
R2-1	24 x 30	5.00	1	5.00	1	5.00	1	5.00	
R3-1	24 x 24	4.00	0	0.00	2	8.00	2	8.00	
R3-2	24 x 24	4.00	1	4.00	0	0.00	1	4.00	
R3-5R	30 x 36	7.50	0	0.00	0	0.00	0	0.00	
R5-1	30 x 30	6.25	12	75.00	12	75.00	12	75.00	
R5-1A	36 x 24	6.00	12	72.00	12	72.00	12	72.00	
R5-18b	48 x 60	20.00	1	20.00	1	20.00	1	20.00	
R5-18c	48 x 48	16.00	1	16.00	1	16.00	1	16.00	
R6-1(L)	36 x 12	3.00	8	24.00	23	69.00	23	69.00	
R6-1(R)	36 x 12	3.00	23	69.00	8	24.00	23	69.00	
R11-2	48 x 30	10.00	2	20.00	2	20.00	2	20.00	
W20-1	36 x 36	9.00	3	27.00	3	27.00	3	27.00	
W20-3	36 x 36	9.00	1	9.00	1	9.00	1	9.00	

CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

RESEARCH PARK DRIVE

IMPROVEMENTS PROJECT

SHEET No.